

DACW-33-85-D-0011 Delivery Order 0018
Roughans Point, Revere, ME

OFFICE COPY DO NOT REMOVE

ATLANTIC TESTING LABORATORIES, LIMITED

Sustaining Member—N.Y.S. Society of Professional Engineers

at

Box 29
Canton, N.Y. 13617
(315) 386-4578

Box 356
Cicero, N.Y. 13039
(315) 699-5281

April 7, 1987

U.S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

Attn: Chief, Engineering Division
NEDED

Re: Subsurface Investigation
Roughans Point, Revere, MA
Contract DACW-33-85-D-0011
Delivery Order No. 0018
ATL Report No. CD020-1-3-87


Gentlemen:

In accordance with Delivery Order No. 0018, dated 25 November 1986, attached is one final copy of our Engineering Report for the subsurface investigation performed at Roughans Point in Revere, MA.

By copy of this letter, we are also transmitting two copies of this report to the Chief of the Geotechnical Engineering Branch.

If you have any questions or comments, please do not hesitate to contact our office.


Respectfully submitted,


Spencer F. Thew, P.E./L.S.
President

SFT/TAB/jm

encs.

2 cc: Chief, Geotechnical Engineering Branch, NEDED-GF



SECTION 1

SUBSURFACE INVESTIGATION
ROUGHANS POINT
REVERE, MA

CONTRACT DACW 33-85-D-0011
CONTRACTING OFFICER:
Edward D. Hammond, LTC, CE
28 June 1985

DELIVERY ORDER NO. 0018
25 NOVEMBER 1986

PREPARED FOR: U.S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

PREPARED BY: Theresa A. Beddoe
Atlantic Testing Laboratories, Limited
P.O. Box 29
Canton, NY 13617

ATL Report No. CD020-1-3-87

March 6, 1987

SECTION 2

TABLE OF CONTENTS

SECTION 1	Title Page
SECTION 2	Table of Contents
SECTION 3	Scope of Investigation <ul style="list-style-type: none">a. Delivery Orderb. Project Sitec. Purposed. Scope of Work
SECTION 4	Quality Control <ul style="list-style-type: none">a. General Certification Statementb. Records Takenc. Equipment Usedd. Procedures
SECTION 5	Summary of Activities and Telephone Log <ul style="list-style-type: none">Table I Summary of ActivitiesTable II Telephone Log
SECTION 6	Chain of Custody Logs
SECTION 7	Safety Reports
SECTION 8	Field Inspector's Logs <ul style="list-style-type: none">a. Figure 1 - General Project Mapb. Figure 2 - Site Location Mapc. Figure 3 - Boring Location Pland. Boring Logs
SECTION 9	Other Records Taken <ul style="list-style-type: none">a. Survey Notesb. Letter to Ms. Dorothy Scholwin

SECTION 3

SCOPE OF INVESTIGATION

a. DELIVERY ORDER NO. 0018

<input checked="" type="checkbox"/> CHECKED BOX APPLIES		<input type="checkbox"/> ORDER FOR SUPPLIES OR SERVICES		<input type="checkbox"/> REQUEST FOR QUOTATIONS NO. RETURN COPY(IES) OF THIS QUOTE BY (THIS IS NOT AN ORDER - See DD Form 1155)		PAGE 1 OF 3	
1 CONTRACT NO. DACW33-85-D-0011		2 DELIVERY ORDER NO. 0011		3 DATE OF ORDER 86 NOV 25		4 REQUISITION PURCH. REQUEST NO. GEB 87-22	
5 ISSUED BY Dept. of the Army New England Division, Corps of Engineers 424 Trapelo Road Waltham, MA 02254-9149 Buyer/Symbol: Kewer/NEDCT-C Phone: Area Code 617-647-8414				7 ADMINISTERED BY (If other than 6)		8 DELIVERY FOB <input checked="" type="checkbox"/> DLSI <input type="checkbox"/> OTHER (See Schedule if other)	
9 CONTRACTOR CODE				10 DELIVER TO FOB POINT BY In accordance with Para. 6 of Attachment 1		11 CHECK IF BUSINESS IS <input type="checkbox"/> SMALL <input type="checkbox"/> SMALL DISADVANTAGE <input type="checkbox"/> WOMEN OWNED	
NAME AND ADDRESS Atlantic Testing Laboratories, Ltd P.O. Box 29 Canton, NY 13617				12 DISCOUNT TERMS NET		13 MAKE INVOICES TO Finance & Accounting Officer at Issuing Office	
14 SERVICES FOR: U.S. Army Engineer Division, New England ATTN: Geotechnical Engineering Branch 424 Trapelo Road Waltham, MA 02254-9149				15 PAYMENT WILL BE MADE BY:		MARK ALL PACKAGES AND PAPERS WITH CONTRACT OR ORDER NUMBER	
16 TYPE OF ORDER: <input checked="" type="checkbox"/> DELIVERY <input type="checkbox"/> PURCHASE				This delivery order is subject to instructions contained on this side of form only and is issued on another Government agency's in accordance with and subject to terms and conditions of above numbered contract.			
17 ACCOUNTING AND APPROPRIATION DATA (LOCAL USE)				furnish the following on terms specified herein, including, for U.S. purchases and delivery as indicated. This purchase is negotiated under authority of			
18 CONTRACT NO. 96X3121 General Investigations AD502304RCOL000 (MB)				19 COPIES SBSA GEB AE/PS COORD MAK/ln			
20 QUANTITY ORDERED ACCEPTED BY		21 UNIT		22 UNIT PRICE		23 AMOUNT	
1. GEOTECHNICAL FIELD INSPECTOR SERVICES		APPROX.		ESTIMATED		24 UNITED STATES OF AMERICA	
1.2 Geotechnical Inspector		120 hr		\$ 40.00		\$ 4,800.0	
1.3 Per Diem -- Overnight Stay		22 day		45.00		540.0	
* If quantity accepted by the Government is same as quantity ordered, indicate by ✓ mark. If different, enter actual quantity accepted below quantity ordered and encircle.				25 TOTAL		\$39,102.5	
26 QUANTITY IN COLUMN 20 HAS BEEN: <input type="checkbox"/> INSPECTED <input type="checkbox"/> RECEIVED <input type="checkbox"/> ACCEPTED, AND CONFORMS TO THE CONTRACT EXCEPT AS NOTED				27 SHIP NO.		28 D.O. VOUCHER NO.	
29 SIGNATURE OF AUTHORIZED GOVERNMENT REPRESENTATIVE				30 PAYMENT <input type="checkbox"/> PARTIAL <input type="checkbox"/> FINAL		31 AMOUNT VERIFIED CORRECT FOR	
32 DATE				33 SIGNATURE AND TITLE OF CERTIFYING OFFICER		34 CHECK NUMBER	
35 RECEIVED AT				36 RECEIVED BY		37 DATE RECEIVED	
38 RECEIVED AT				39 RECEIVED BY		40 TOTAL CONTAINERS	
41 RECEIVED AT				42 RECEIVED BY		43 S/R ACCOUNT NUMBER	
44 RECEIVED AT				45 RECEIVED BY		46 S/R VOUCHER NO.	

CONTINUATION SHEET

REF. NO. OF DOC. BEING CONT'D
Delivery Order No. 0018
to DACW33-85-D-0011

PAGE 2 OF 3

NAME OF OFFEROR OR CONTRACTOR

Atlantic Testing Laboratories, LTD

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
		APPROX.			ESTIMATED
1.4	Mileage from Waltham, MA & Return	75	MI	.35	\$ 26.25
2.0	GEOTECHNICAL SERVICES AND REPORT				
2.1	Geotechnical Report	1	JOB	60% of Line Item 1.2	2,880.00
3.	SURVEYING				
3.1	Mobilization and Demobilization	1	JOB	180.00	180.00
3.2	Mileage from/to Waltham, MA	25	MI	.35	8.75
3.4	Survey Crew and equipment	1	DAY	440.00	440.00
3.5	Overnight per diem for survey crew	1	DAY	90.00	90.00
3.6	Data Reduction and Plotting	1	JOB	100% of Line Item 3.4	440.00
3.7	Standby Time	4	HR	55.00	220.00
6.	MOBILIZATION AND DEMOBILIZATION ONE DRILL RIG, CREW AND AUXILIARY EQUIPMENT				
6.1	Mobilization and Demobilization	2	JOB	700.00	1,400.00
6.2	Mileage from/to Waltham, MA	50	MI	1.15	57.50
6.5	Standby time/on site moves	80	HR	75.00	6,000.00
9.	BULLDOZER EXCAVATION AND GRADING				
9.1	Bulldozer (150 H.P.) with operator	40	HR	70.00	2,800.00
10.	FLOATING PLANT ATTENDANT VESSEL, CREW AND EQUIPMENT				
10.2	16 ft. boat	6	DAY	60.00	360.00
10.7	Mobilization and Demobilization for 320 square foot float	1	JOB	950.00	950.00
12.	AUGER BORINGS - UNCASSED				
12.3	Hollow Stem Auger, 4" inside diameter	390	LF	22.00	8,580.00

CONTINUATION SHEET

Delivery Order No. 0018
to DACW33-85-D-0011

3 3

NAME OF OFFEROR OR CONTRACTOR

Atlantic Testing Laboratories, LTD

ITEM NO Contract line	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
		APPROX.			ESTIMATED
13.	DRIVE SAMPLE BORING (SPT) WITHOUT CASING				
13.1	0-30 ft. depth	12	EA	13.00	\$ 156.00
16.	THIN WALLED TUBE SAMPLING				
16.1	3-inch diameter x 30 inch Tube	6	EA	110.00	660.00
18.	DRIVING AND PULLING CASING				
18.2	HX, and 6-inch size	96	LF	28.00	2,688.00
22.	DIAMOND CORE DRILLING VERTICAL				
22.3	NWX size and/or NWM	10	LF	45.00	450.00
32.	Crane and Operator	6	DAY	896.00	5,376.00
<p>You are authorized to commence work on this Delivery Order on December 8, 1986.</p>					

ATTACHMENT 1

CONTRACT NO. DACW33-85-D-0011

DELIVERY ORDER NO. 0018

EXPLORATION INSTRUCTIONS

PROJECT: Roughans Point Coastal Flood Protection Study

SITE: Roughans Point, Revere, MA

PURPOSE: Determine foundation conditions for proposed revetments, sluice gate and earth berm.

1. SCOPE OF INVESTIGATIONS

a. General.

Locate and execute twenty-three (23) drive sample borings by means of tape measuring the given distances as shown on Attachment No. 2.

b. Explorations.

(1) All explorations shall be located by the geotechnical inspector tape measuring from features shown on the Exploration Plan (Attachment No. 2). Elevations shall be determined by Contractor-provided survey crew.

(2) The twenty-three (23) drive sample borings shall be to the following depths and subject to the provisions below: FD-A, 15'; FD-B, 25'; FD-C, 15'; FD-D, 25'; FD-E, 15'; FD-F, 25'; FD-G, 15'; FD-H, 25'; FD-I, 15'; FD-J, 25'; FD-K, 15'; FD-L, 25'; FD-M, 15'; FD-N, 15'; FD-O, 50'; FD-P, 20'; FD-Q, 50'; FD-R, 20'; FD-S, 30'; FD-T, 20'; FD-U, 30'; FD-V, 15'; and FD-W, 25'. If organic materials (peat, organic silt, etc.) are still encountered at the above-specified depths, the Contractor shall notify the Government at whose discretion the borings shall be continued to fully penetrate the organic materials or to other depths as directed. If borings FD-O and FD-Q do not fully penetrate cohesive materials (silty clays, sandy clays, etc), the Contractor shall notify the Government at whose discretion the borings shall be continued to fully penetrate the cohesive materials or to other depths as directed. Payment for approved additional boring shall be made at established unit prices. If refusal is encountered in the top 15 feet of a borehole, the boring shall be continued using vertical diamond coring drilling until the hole can be completed using drive sampling methods or the required depth is reached. Boreholes shall be terminated prior to the required depth if refusal is encountered below 15 feet or below the organic materials.

(3) Standard Penetration Tests shall be taken at 5-foot intervals in the boreholes in accordance with Part II, para. 13 of the specifications. Undisturbed samples shall be taken between standard penetration tests at 10-foot intervals below the organic materials in boreholes FD-O and FD-Q, in accordance with Part II, para. 16 of the specifications.

c. Inspection. A geotechnical inspector shall act as field inspector while performing the borings. The inspector shall provide telephone reports to Mr. Ronald DeFilippo, Corps of Engineers at tel. (617) 647-8175 at least once each working day. The alternate point of contact is Mr. Paul Schimelfenyg, Corps of Engineers tel. (617) 647-8394.

d. All samples shall be delivered to the Corps of Engineers Headquarters in Waltham, Massachusetts. Sample delivery shall be coordinated with the Director, NED Materials and Water Quality Laboratory at tel. 617-647-8367/8392.

2. SITE CONDITIONS.

The proposed exploration program is along the Atlantic Ocean coast at Roughans Point, Revere, Massachusetts. Twenty-one of the proposed explorations are relatively flat beach areas some of which are subjected to tidal action. One proposed exploration is on a traffic island. One proposed exploration is in a marsh area. Subsurface information is shown on Attachment No. 3.

3. RIGHTS-OF-ENTRY.

Rights-of-entry will be arranged by the Contractor in cooperation with the City of Revere, Mr. Frank Stringi at tel. (617) 284-3600, ext. 111, and the Metropolitan District Commission, Mr. Henry Higgins at tel. (617) 727-7220.

4. COORDINATION.

The Contractor shall provide five days notice prior to start up of exploration activity to Mr. Ronald DeFilippo, Corps of Engineers at tel. (617) 647-8175 and Mr. Frank Stringi, City of Revere, Massachusetts at tel. (617) 284-3600, ext. 111. The alternate point of contact is Mr. Paul Schimelfenyg, Corps of Engineers at tel. (617) 647-8394.

5. EXPLORATION NUMBERS.

The boring locations designated FD-A through FD-W shown in Attachment No. 2 shall be redesignated FD-1 through FD-23 in order of their completion.

6. COMPLETION SCHEDULE


Services under this delivery order shall start within fifteen days after the receipt of the delivery order. Duration of the drilling effort is estimated to be eighteen calendar days. The geotechnical report shall be submitted in draft form for review, to the Government, postmarked no later than seven calendar days after completion of the field work.



Government review will take approximately ten calendar days from receipt of draft report. The final geotechnical report shall be submitted postmarked no later than seven calendar days after receipt of draft report with Government comments.

7. QUALITY CONTROL

You will be held responsible for the quality of the maps submitted and for all damages caused the Government as a result of your negligence in the performance of any services furnished under the contract.

Although submissions required by your contract are technically reviewed by the Government, it is emphasized that your work must be prosecuted using proper internal controls and review procedures. The letter of transmittal for each submission which you make shall include a certification that the submission has been subjected to your own review and coordination procedures to ensure (a) completeness for each discipline commensurate with the level effort required for that submission, (b) elimination of conflicts, errors, and omissions, and (c) the overall professional and technical accuracy of the submission. Documents which are significantly deficient in any of these areas will be returned to you for correction and/or upgrading prior to our completing our review.





BORING NUMBER	DATE	ORGANIZATION
7	1910	MASS DEPT PUB WKS (P)
8	1916	MASS DEPT PUB WKS
17	1919	MASS DEPT COAST
18	1962	MASS DEPT TEST BORING CO
20	1962	MASS DEPT COAST (P)
21	1971	FAY, SPOFFORD, & THORNDIKE

- LEGEND**
- Water Level (Tidal)
 - Assumed material boundary
 - Material boundary defined by boring
 - Lack of corroborative subsurface data
 - Boring indicating number and depth

GRAPHIC SCALES

HORIZONTAL
1" = 10'

VERTICAL
1" = 10'

NOTIONAL REPRESENTATIVE VERTICAL DEPTH OF 1910
12' MVD - 10' FEET MVD

DEPARTMENT OF THE ARMY
ENGINEERING DISTRICT NO. 1
MASSACHUSETTS

REVERSE COASTAL
FLOOD PROTECTION STUDY
MASSACHUSETTS

ROUGHANS POINT
PROFILE OF EXPLORATIONS

b. Project Site

The site of the subsurface explorations is along the Atlantic Ocean coastline at Roughans Point, Revere, MA. Twenty-one of the explorations are located on relatively flat beach areas, most of which are subjected to tidal action. One exploration is on a traffic island, and one is in a marsh area. A general Project Map and Site Location Map are included in Section 8.

c. Purpose

The subsurface investigations were to determine foundation conditions for proposed revetments, sluice gate and earth berm.

d. Scope of Work

Inspection and exploration instructions, which were provided by the Army Corps of Engineers, New England Division, are included in Section 3a.

Work under this delivery order consisted of locating twenty-three drive sample borings by means of tape measuring the given distances shown on the Exploration Plan, Attachment No. 2 of the delivery order (Section 3a). Two borings (FD-W, FD87-14, and FD-V, FD86-1) were relocated due to site access problems; the remainder of the borings were completed within a five foot radius of the requested locations. A boring location plan is in Section 8c. The ground elevation was determined by an Atlantic Testing Laboratories' survey crew. Elevations were established from an existing benchmark located at an angle point in the existing seawall, near station 56+00. The explorations were performed in accordance with paragraphs 12, 13, 16, 18 and 22 of the contracted "Specifications for Services and Equipment Necessary for Conducting Geotechnical Exploratory Work, Various Locations in New England and New York". Specific instructions and changes during the course of the work were given verbally in telephone conversations with a Corps of Engineers representative and are documented in Section 5.

SECTION 4

QUALITY CONTROL

a. General Certification Statement

I hereby certify that the records, equipment and procedures mentioned below were used to perform the subsurface exploration described herein. I also certify that the work was performed in a professional manner and meets the requirements set forth in the delivery order. This report has been subject to my review and is both complete and technically accurate.

CERTIFIED 6 March 1987


Spencer F. Thew, P.E./L.S.

b. Records Taken

Pertinent drilling procedures, sampling operations, and soil classifications were noted on the following forms provided for use by the Corps of Engineers:

- NED 121 - Field Log of Test Boring, Summary
- NED 58 and 58a - Field Log of Test Boring
- NED 74 - Field Log of Undisturbed Sampling in Drill Holes
- NED 59 - Subsurface Water Observations and Boring Location Sketch

A complete series of logs for each of the borings is included in Section 8d.

Disturbed sample containers were labeled using ENG Form 1742. Undisturbed sample tubes were labeled using ENG Form 1743. A summary of daily activities and a telephone log are Tables I and II of Section 5, respectively. A chain of custody log is in Section 6. The Safety Meeting Reports, NED Form 251, including exposure time for Atlantic Testing Laboratories' personnel, are located in Section 7.

c. Equipment Used

All equipment and supplies were provided by Atlantic Testing Laboratories, Limited, with the exception of a Komatsu Track Backhoe and Caterpillar D-9, provided by a subcontractor.

1. Survey Equipment

- Wild Heerburg T-1A 20-second, erect-image theodolite
- Wild Heerburg NAK-2 automatic level
- 25' fiberglass telescoping stadia rod
- fluorescent paint, flagging, nails
- 2" x 4" x 4' long stakes

2. Drilling Equipment

- skid-mounted CME45 drill rig on trailer
- track-mounted CME45 drill rig
- 1-3/8" I.D. by 2 ft long split spoon samplers
- 140 pound hammer
- 3" I.D. by 30" long thin-walled tube samplers
- AW sized rods used to advance the samplers
- 3-1/4" I.D. hollow stem augers
- 4" I.D. casing with spin shoes
- 3-7/8" and 3-1/8" roller bits
- 3" O.D. by 5 ft diamond bit core barrel
- NW sized rods used to advance the roller bit and core barrel

d. Procedures

1. Survey Procedures

On January 5 and 6, 1987, a two man field crew of Atlantic Testing Laboratories staked out soil borings FD-A through FD-W (FD86-1, FD87-1 through FD87-22). Boring locations were established by taping distances given on Attachment No. 2 of the delivery order. The locations were taped from the landward edge of the existing wall or by extending the line of the existing wall. Borings FD-V (FD86-1) and FD-W (FD87-14) were located

as indicated on the exploration plan, but moved slightly due to access problems. FD-V was requested in the center of a four lane highway, and was moved to the adjoining traffic island to minimize safety hazards. FD-W was requested in the center of Sales Creek next to a concrete abutment; it was moved to the other side of the abutment and correspondingly deepened to compensate for the elevation difference.

Elevations were established on January 6, 1987, on the above borings from an existing benchmark located at an angle point in the existing seawall, near stations 56+00 and boring FD-S (FD87-20). The reference benchmark is a chiselled square in the top of the seawall. The reference elevation is 17.31 ft mean sea level. A closed level loop was run on the soil borings proceeding from the benchmark north and west along the coast to FD-A (FD87-5), south to Winthrop Parkway and southeast along the Winthrop Parkway to the benchmark. The elevations of borings FD-V (FD86-1) and FD-W (FD87-14) were determined from a temporary benchmark established on the first loop.

These elevations are accurate only for the day they were established. Subsequent tides and a series of violent storms altered the beach profile to one more typical of the winter (i.e. a stony, steep face). However, the elevations should indicate actual boring elevations to within one half foot. The borings most probably affected are the eight borings along Reach E and Reach F, FD-N through FD-U (FD87-15 through FD87-22).

2. Drilling Procedures

Borings FD-O (FD87-15), FD-Q (FD87-21), FD-S (FD87-20) and FD-U (FD87-22) were located in the large boulder rip rap directly at the base of the seawall. These were cleared by a subcontractor with a Komatsu Track Backhoe. After the borings were completed, the subcontractor returned to the site to replace the boulders and return the rip rap to its original condition. This work has been inspected and is complete. Boring FD-W (FD87-14) was cleared of small trees by a subcontracted Caterpillar D-9, which also cleared a road down to the boring location. This work had been cleared with a representative of the property owner, Mr. Robert Cerretani.

Twenty of the borings were advanced using 3-1/4" I.D. hollow stem augers to 2 ft above specified depth. The final 2 ft of the borings were completed by sampling. The augers were cleaned out, when necessary, with a water hose prior to sampling. Boring FD-U (FD87-22) was advanced to 11.0 ft using hollow stem augers and completed using a 3-1/8" roller bit in the open hole. Borings FD-O (FD87-15) and FD-Q (FD87-21) were advanced to 30.0 ft and 20.0 ft respectively by spinning 4" casing and washing out with a 3-7/8" roller bit. A 3-1/4" I.D. hollow stem auger was used to start FD-O (FD87-15). These two borings were continued to 2 ft short of completion by advancing the 3-7/8" roller bit in the open hole. The final two ft of the borings were completed by sampling.

All the borings were completed at the specified depths, except for FD-O (FD87-15) and FD-Q (FD87-21) which were deeper than requested and FD-T (FD87-19) and FD-U (FD87-22) which were shallower than requested. These changes were authorized by the Corps of Engineers (see Section 5). FD-W (FD87-14) was deepened to terminate at the requested elevation in order to accommodate its new location, which was requested by Atlantic Testing Laboratories.

Standard penetration testing sampling was accomplished using a 1-3/8" I.D. by 2 ft long split spoon sampler advanced by a 140 pound hammer dropping in free fall from a height of 30", in accordance with ASTM D-1586. The sampling interval was 5 ft. Refusal was defined as 100 blows in less than 18 inches or bouncing refusal. The soil samples were placed in 16 oz glass jars with hermetically sealed lids. The samples were not classified in the field because of freezing or near freezing temperatures wind/chill factor. The samples were brought to room temperature and classified in accordance with ASTM D-2488. Jars were labeled using ENG Form 1742, provided by the Corps of Engineers.

Thin-walled tube sampling was performed using a 3" I.D. by 30" long tube advanced into undisturbed soils using a steady downpressure provided by the rig, in accordance with ASTM D-1587. The sampler was allowed to set for 10 minutes, given one full twist and extracted. The base of the tube was capped, taped and sealed in beeswax. Disturbed material was removed from the top of the tube and used for sample classification in accordance with ASTM D-2488. The top of the sample was capped in the tube with beeswax. The remainder of the tube was filled with beach sand; the tube was capped, taped and sealed with beeswax. The tubes were labeled with ENG Form 1743 and placed in an undisturbed sample shipping box, provided by the Corps of Engineers.

Chain of Custody Logs were maintained documenting custody of the samples between Atlantic Testing Laboratories and the Corps of Engineers. All samples were delivered to the USACE NED Materials and Water Quality Laboratory.

Fourteen of the twenty-three borings were completed in the first four days of drilling effort. The completion of the remainder of the borings was hampered by several factors:

1. A property owner, Ms. Dorothy Scholwin, denied ATL access across her beachfront property which extended to mean low water. Access was granted January 12, 1987 after she received a written request for access (included in Section 9b).
2. The winter storm season began December 31, 1986 and battered the coastline with an unusually great number of storms. Two drilling days were generally lost to each storm, the day of the storm itself and the day after, when the storm surge from the storm center in the Atlantic Ocean remained high.
3. The remainder of the borings were along Reach E and Reach F and were affected by the tides. Access to these borings was rendered brief by the tides; at most a five hour work shift was possible between high tides. This five hour shift was further shortened when low tide did not correspond to the brief daylight hours. The height of low tide also had an effect on the number of hours worked; when low tide was high, access was not possible. When the tides permitted two work periods during the day, one in the early morning and one in the early evening, lights were used. However, because of the residential neighborhood, work was not possible before 6:30 AM or after 11:00 PM.

These factors resulted in an unusually long completion period for the job. Section 5 contains a Summary of Activities, which includes daily tide and storm information.

SECTION 5

**SUMMARY OF ACTIVITIES
AND
TELEPHONE LOG**

TABLE I

Summary of Activities

NOTE: On-site hours reflect inspector's on-site time.

Tide information gives time of high or low tide/height of the tide in feet referenced to mean low water for Boston Harbor (from 1987 Tide Tables for East Coast of North and South America, U.S. Dept. of Commerce, NOAA, National Ocean Service).

Weather information is provided to reflect the influence of storms on drilling activity.

<u>Date</u>	<u>Activity</u>
December 29	Monday: <ul style="list-style-type: none">- Mobilize inspector TA Beddoe, two drillers, skid-mounted CME 45 and raft to site.
December 30	Tuesday: on-site 7:00-5:00 <ul style="list-style-type: none">- Weather: cool (30's), overcast, windy.- Locate Roughans Point, investigate site for access.- Pat Sullivan, Manager, ATL Subsurface Exploration Division, on-site for site reconnaissance.- Stake out borings V, W, B, C.- Repair flat tire on skid rig's trailer.- Unload drilling material at Roughans Point.- Investigate site re: necessity of crane to lower rig over wall. All that will necessary is a track vehicle to move the rig while the tide is out.- Conduct safety meeting.
December 31	Wednesday: on-site 7:00 - 10:30 <ul style="list-style-type: none">- Weather: overcast, cool (30's), windy.- Complete boring FD86-1 (V).
January 5	Monday: on-site 12:00 - 4:30 <ul style="list-style-type: none">- Weather: clear, upper 30's, breezy.- Tide: 0908/-0.1, 1523/9.9- Travel to site.- Survey crew stake out borings FD-A, B, C and E. Begin taping distances along seawall for remainder of borings.- Meet Ms. Dorothy Scholwin, 156 Broad Sound, 289-5529 who denied us access to the last six borings. ATL cannot cross her beachfront with our equipment.- Immediately thereafter we were denied access along the seawall when a property owner wired the fence shut. He allowed us to cut the wires provided we wire the fence shut when finished. His big concern was his liability if a child fell off the seawall onto the rocks below.- Mobilize track-mounted CME45 to site.

<u>Date</u>	<u>Activity</u>
January 6	<p>Tuesday: on-site 7:00 - 4:00</p> <ul style="list-style-type: none"> - Weather: clear, warm (upper 30's), slightly breezy. - Tides: 1006/0.3, 1622/9.2 - Stake out remainder of borings. - Run level survey of boring locations to obtain elevations. - Complete borings FD87-1 through FD87-6 (FD-A, B, C, D, E, F). - Hold safety meeting. - Standby time 1 hour for call to Corps (track rig).
January 7	<p>Wednesday: on-site 7:00 - 5:00</p> <ul style="list-style-type: none"> - Weather: partly cloudy, breezy, 40's - Tides: 0457/9.4, 1107/0.5, 1721/8.6. - Delay in morning due to high water. Investigate the remainder of the boring locations with respect to access problems. - Possible subcontractor on site to investigate boring locations FD-O, Q, S, U, W re: clearing access to them. - Complete FD87 - 7, 8, 9 (FD-G, H, I). FD87-10 (J) abandoned at 20' due to rising tide. Augers could not be left in the hole because of flowing sands.
January 8	<p>Thursday: on-site 7:00 - 5:00</p> <ul style="list-style-type: none"> - Weather: clear, 30's, windy, raw. - Tides: 0551/9.3, 1212/0.6, 1825/8.2. - Complete borings FD87-10, 11, 12, 13 (FD - J, K, L, M). - Ron DeFilippo and Paul Schimelfenyg on site. Showed them Ms. Scholwin's property and problematic boring locations, spoke about access problems. - Possible subcontractor did not contact ATL. - Note large amounts of standby time will be used because of the tides, especially next week.
January 9	<p>Friday: on-site 7:00 - 3:00</p> <ul style="list-style-type: none"> - Weather: clear, 30's breezy. - Tides: 0647/9.2, 1312/0.6, 1926/7.9. - Telecons to Corps, Canton, City of Revere Assessor's Office, Landmark Engineering & Surveying, Inc., Suffolk Registry, Revere lawyer Edward J. Leach, Ms. Dorothy Scholwin regarding blocked access to last six borings. - A letter requesting an easement was sent via Federal Express to Ms. Dorothy Scholwin from ATL corporate headquarters, Canton, NY. This letter is included in Section 9b. - No drilling accomplished as air transportation for the weekend had been cancelled. - Retained services of Caruso Construction Company, Charlie Connor, Principal, to provide track backhoe and D-9 to clear access to borings FD-O, Q, S, U, W. - Obtain clearance from Mr. Robert Cerretani to complete boring W, including cutting trees to build a road for access. - Standby time 5 hours for the tide (skid and track rigs).

<u>Date</u>	<u>Activity</u>
January 12	<p>Monday: on-site 4:00 - 5:30</p> <ul style="list-style-type: none"> - Weather: overcast, 30's, windy. - Tides: 0916/9.4, 1546/0.2, 2158/8.0. - Travel to site. - Subcontractor cleared access to FD-0. - Dorothy Scholwin gave verbal permission to cross her property after having received the letter written by ATL. - Will try to complete FD-N, P, R, T, W. After these seaward borings have been completed, the rip rap can be cleared for access to the remaining borings along the seawall.
January 13	<p>Tuesday: on-site 6:30 - 7:00</p> <ul style="list-style-type: none"> - Weather: clear, 30's, windy, raw. - Tides: 1001/9.5, 1626/0.1, 2240/8.1. - Hold safety meeting. - Unable to accomplish any drilling because of tides. Little work will be accomplished this week because of them. - Move rigs to pull-out in order to move on FD-W tomorrow. - Subcontractor cleared access to FD-W. - Standby time 8 hours for the tide (skid and track rigs).
January 14	<p>Wednesday: on-site 7:00 - 1:00</p> <ul style="list-style-type: none"> - Weather: clear, breezy, upper 30's. - Tides: 1040/9.6, 1705/0.0. - Complete FD86-14 (FD-W). - Track-mounted CME45 demobilized to Winnepesaukee. - Return travel to Canton. - Standby time 8 hours for the tide (skid rig)
January 19	<p>Monday</p> <ul style="list-style-type: none"> - Weather: storm in progress. - Travel to site. - Track-mounted CME45 mobilized from Winnepesaukee to Revere. Hauler requires maintenance. - Standby time 4 hours due to tide/weather (skid rig)
January 20	<p>Tuesday: on-site 7:00 - 5:30</p> <ul style="list-style-type: none"> - Weather: clear, 20's, breezy. - Tides: 0831/0.6, 1437/9.1. - Sea high (about 1 ft higher than normal) because of storm now off the coast. The 4 to 8 inches of snow received last night did not significantly impede our progress. - Advance FD87-15 (FD-0) to 12 ft using augers. Pulled augers when the tide forced us off the site. We will spin casing tomorrow. - Could not access FD-N due to high water. - Conduct safety meeting. - Standby time 4 hours due to tide (skid and track rigs)

<u>Date</u>	<u>Activity</u>
January 21	<p>Wednesday: on-site 7:30 - 7:30</p> <ul style="list-style-type: none"> - Weather: high 30's, overcast, light breeze. - Tides: 0919/0.6, 1524/8.8. - Unable to access FD-0 with skid rig. Access to other borings with the skid rig not possible because of high seas. - Complete FD87-16 (FD-N) using track-mounted rig. - Skid-mounted CME45 demobilized to Winnepesaukee. - Note heavy breakers due to approaching storm.
January 22	<p>Thursday: on-site 7:00 - 12:00</p> <ul style="list-style-type: none"> - Weather: overcast, windy, 20's. - Tides: 1009/0.5, 1618/8.5. - Complete FD87-17 (FD-R). - Ron DeFilippo on-site <ul style="list-style-type: none"> - Delivered seven boxes of samples to him. - Authorized boring termination when it became apparent that the silts and clays were interbedded with organics. The last sample did terminate in sandy silt. - Emphasized the importance of hard hats. - Requested frequent checking of the 30" hammer drop to ensure it is correct. - Storm brought strong east winds at the end of the boring; rising tide forced us off-site. - Left Boston to return to Canton at 1:30. We determined that the storm would render work Friday impossible.
January 26	<p>Monday:</p> <ul style="list-style-type: none"> - Weather: frigid, windy, heavy snow with clearing in the afternoon. - Travel to site. - Note vandalism to rig: spark plug wires had been pulled and gauges broken. No serious damage had been done.
January 27	<p>Tuesday: on-site 8:00 - 1:00</p> <ul style="list-style-type: none"> - Weather: clear, windy, heavy seas. - Tides: 0837/10.7, 1510/-1.2. - Conduct safety meeting. - Attempt to access borings, but high seas with breakers topping the walls and localized flooding kept the boring locations inaccessible. - Work on repairing the rig. - Find a marine forecast that indicated we might be able to access the borings tomorrow. - Standby time 4.5 hours due to tide (track rig).

<u>Date</u>	<u>Activity</u>
January 28	<p>Wednesday: on-site 9:00 - 5:30</p> <ul style="list-style-type: none"> - Weather: clear, 20's, light breeze - Tides: 0935/11.1, 1607/-1.6. - Rig repair completed. - Complete FD87-18 (FD-P) - Drill 11.75' of FD87-19 (FD-T) before tide forced us to vacate. Entire depth of boring was in dense, sandy till. - Lynn Mazzarella, 149 Endicott Avenue, Revere, stopped by to request that when the rip rap is placed by the public stairs, a path be left open so that elderly people can access the beach easily. Do not block the stairs with a huge boulder, as had been done before. - Standby time 2.5 hours due to tide (track rig).
January 29	<p>Thursday: on-site 9:00 - 5:30</p> <p>Weather: clear, light breeze.</p> <ul style="list-style-type: none"> - Tides: 1033/11.4, 1701/-1.9. - Access FD87-15 (FD-0) after removing a large boulder which had fallen in. Spin 10' of casing. Attempt to sample at 15' (10' from surface) yielded no recovery due to surface gravel which remained in the casing. We did not have the proper roller bit for clearing out casing. We will clean out Tuesday and resample, either at 15 or 17 ft. Darkness forced us off-site. - Standby time 1.5 hours due to tide (track rig).
January 30	<p>Friday:</p> <ul style="list-style-type: none"> - Return travel to Canton.
February 2	<p>Monday:</p> <ul style="list-style-type: none"> - Travel to job site. - Minor vandalism noted. Fifty feet of fire hose stolen.
February 3	<p>Tuesday: 7:00 - 10:30</p> <ul style="list-style-type: none"> - Weather: cloudy, high 30's, sprinkles in mid-morning, clearing at noon. - Tides: 0841/-0.5, 1455/9.6, 2103/-0.4. - First Shift: Advance FD87-15 (FD-0) 9 ft before returning tide forced us off. - Ron DeFilippo on-site to witness undisturbed sampling. He had expected piston sampling and indicated that that might be requested. Would determine if we could terminate FD87-15 (FD-0) early if we have encountered till. He delivered a formal definition of density terms to be used on the boring logs. - Hold safety meeting. - Rent a bank of lights so that we will be able to work at night. - Second Shift: Advance FD87-15 (FD-0) 8 ft to 32 ft. Note trouble with recovery of soils.

<u>Date</u>	<u>Activity</u>
February 4	<p>Wednesday: on-site 7:00 - 11:00</p> <ul style="list-style-type: none"> - Weather: partly sunny, flurries, mild. - Tides: 0935/0.0, 1548/8.9, 2153/0.3. - Subcontractor on-site. Cleared FD-Q, partially cleared FD-U and FD-S. - First Shift: Have trouble with trash pump. Advance FD87-15 (FD-0) 10 ft to 42 ft. The rig shifted during drilling which slightly bent 10 ft of NW rod. - Second Shift: Advance FD87-15 (FD-0) to 48.5 ft, taking one undisturbed sample. Material which caused refusal of tube was sampled. Recovered a grey till-like material. Will take another sample at 50 ft.
February 5	<p>Thursday: on-site 7:30 - 12:30</p> <ul style="list-style-type: none"> - Weather: clear, windy, cold-frigid. - Tides: 1032/0.4, 1745/7.7. - Drill using roller bit to 49 ft through dense material. Water swivel seized up, so we stopped short of 50 ft to take a sample. Sample from 49-51 ft and recover gravelly sand. Drill to 52 ft, noting problems with water pressure and the swivel. The swivel broke at 52 ft and we terminated drilling. Noted caving at 50 ft. - We will have problems maintaining an open hole without a decent flow of water and a water swivel. We rented a better trash pump. Canton will ship a new water swivel. - We will work the weekend, drilling FD-S and FD-U until the water swivel comes in.
February 6	<p>Friday: 8:00 - 1:00</p> <ul style="list-style-type: none"> - Weather: clear, warm (30's), breezy. - Tides: 1131/0.8, 1745/7.7. - Subcontractor on-site, cleared access to FD-S and FD-U. - Complete FD87-20 (FD-S), intersecting no great thickness of till. - Water swivel not received. It is being sent Federal Express.
February 7	<p>Saturday: 9:30 - 2:30</p> <ul style="list-style-type: none"> - Weather: Clear, warm (40's). - Tides: 0603/8.8, 1233/1.0, 1842/7. - Attempt to access FD-U, but low tide was too high. We flooded the engine in the attempt. - Water swivels arrived too late to enable us to access FD87-15 (FD-0).
February 8	<p>Sunday: 10:30 - 3:00</p> <ul style="list-style-type: none"> - Weather: clear, warm (30's) - Tides: 0701/8.7, 1336/1.0, 1974/7.4. - Complete FD87-15 (FD-0), noting difficulty with caving. Also, as water pressure was not great, had difficulty flushing sandy particles out of the hole. Pull casing. - Standby time 1.5 hours due to approaching storm.

<u>Date</u>	<u>Activity</u>
February 9	<p>Monday: 11:00 - 12:30</p> <ul style="list-style-type: none"> - Weather: violent storm in progress. - Tides: 0758/8.8, 1432/0.8. - Information from tide table allowed us to schedule work for the remainder of the week and next week. - On-site to break casing and attempt boring access, but the heavy snowstorm with high winds coupled with a high low tide thwarted us.
February 10	<p>Tuesday: 12:00 - 1:00</p> <ul style="list-style-type: none"> - Weather: clear, sunny, windy, cold - 20's. - Tides: 0850/9.0, 1520/0.6. - Pick up copy of tide tables in Boston. - On-site to attempt access, but storm surge too great. Height of tide combined with calm sea should allow access tomorrow as expected. - Hold safety meeting.
February 11	<p>Wednesday: 12:30 - 5:30</p> <ul style="list-style-type: none"> - Weather: sunny, windy, cold (low 30's). - Tides: 0938/9.2, 1602/0.3. - Advance FD87-21 (FD-Q) from 0.0 to 12.0 ft.
February 12	<p>Thursday: 2:00 - 6:30</p> <ul style="list-style-type: none"> - Weather: overcast, still, low 30's. - Tides: 1020/9.5, 1640/0.0. - Travel to Waltham USACE NED HQ to deliver four boxes of samples to the Materials and Water Quality Laboratory. - Pick up copies of ENG Form 1743, and undisturbed sample shipping box, which they provided. - Advance FD87-21 (FD-Q) 10' from 12 to 22 ft. - Begin travel to Canton.
February 16	<p>Monday: on-site 5:00 - 9:00</p> <ul style="list-style-type: none"> - Tides: 0640/0.0, 1250/9.7, 1903/-0.5. - Note inspector change to PM Fisher. - Conduct safety meeting. - Complete FD87-22 (FD-U) at 22.5' after drilling through 10 ft of till.
February 17	<p>Tuesday: on-site 7:00 - 9:00</p> <ul style="list-style-type: none"> - Tides: 0722/-0.1, 1330/9.6, 1941/-0.3. - First Shift: Moved onto FD87-21 (FD-Q) but did not advance the boring due to cold weather and mechanical problems. - Repaired rig. - Second Shift: Advanced FD87-21 (FD-Q) from 22 to 32 ft.

Date Activity

- February 18 Wednesday: on-site 6:00 - 10:30
- Tides: 0804/-0.2, 1412/9.3, 2022/-0.1.
 - First Shift: Advance FD87-21 (FD-Q) from 32 to 35 ft.
Develop pump problems.
 - Subcontractor on-site to replace rip rap.
 - Second Shift: Noted vandalism of rig during the day.
Advanced FD87-21 (FD-Q) from 35 to 50 ft.
- February 19 Thursday: on-site 7:00 - 2:00
- Tides: 0852/-0.1, 1458/8.9.
 - Completed FD87-21 (FD-Q) at 56.5 ft.
 - Picked up equipment.
 - Track-mounted CME45, inspector demobilized to
Winnepesaukee.
- February 21 Saturday:
- Subcontractor completed rip rap replacement.
- February 23 Monday:
- Samples delivered to USACE NED Materials and Water
Quality Laboratory.
- February 25 Wednesday: 12:45 - 1:45
- Quality of rip rap replacement inspected by Gregory Craig
of ATL's Manchester, New Hampshire office, as directed by
the inspector. Job appears neat and complete.

TABLE II

Telephone Log

<u>Date</u>	<u>Conversation</u>
December 30	<p>Tuesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Utility clearance for FD-V: Corps felt that if boring was performed at or near the grassy area and not as requested on Attachment No. 2 of the delivery order, no utility clearance was necessary. Corps authorized moving boring to grassy area. - Position of borings along the seawall. Locations are referenced from the landward side of the crest of the seawall. No borings would be on the wall. Inspector realized later that the structure emphasized on Attachment No. 2 is the future and not the present seawall.
December 31	<p>Wednesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Completion of boring FD86-1 (V) though we did not intercept an organic layer? Corps authorized boring termination. - Numbering boring FD-V FD86-1 and the remaining borings FD87-1 through FD87-22 in accordance with previous procedure? Yes. - ATL will need more jar sample labels.
January 5	<p>Monday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Re: access problem created by Ms. Dorothy Scholwin. Recommended calling Frank Stringey, City of Revere, or Dennis Wascowitz, USACE if the city could not help.
January 5	<p>Monday: Frank Stringey, City of Revere</p> <ul style="list-style-type: none"> - The city of Revere was familiar with Ms. Scholwin. Call him later in the week to see what progress he has made.
January 6	<p>Tuesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - No organics found in FD-E or FD-F. Can we terminate? Yes. Call the Corps only if the borings are still in the organic layer at the requested completion depth. - Is the benchmark near FD-S indicated on Attachment No. 2 of the delivery order proper to use to establish the elevations of the borings? Yes.
January 7	<p>Wednesday: Frank Stringey, City of Revere</p> <ul style="list-style-type: none"> - Corps will need to obtain a temporary restraining order to give us access across Ms. Scholwin's property. - A recent change in property laws may have redefined the seaward edge of her property, but he is not sure how.
January 8	<p>Thursday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Overrun on surveying charge by 0.5 days. Because this job was bid separately from our main contract, we can only charge the Corps those quantities in our proposal. - Expect him on-site today. - Re: temporary restraining order: The Corps will start working on it immediately.

<u>Date</u>	<u>Conversation</u>
January 9	<p>Friday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Re: Ms. Scholwin: Corps is presently exploring two avenues: (1) trying to obtain a navigational right to the high tide mark and (2) talking to the commonwealth of Massachusetts to gain an understanding of State Law. It is ATL's responsibility to attempt to obtain an easement through her property. If we should retain her for an easement, we will be reimbursed (Section 4, Paragraph F of the Specifications). - Corps wanted to know why we did not want to use a crane. (1) To use the crane, we would have to secure permission from at least four land owner's to allow us access to the wall. Gaining this access is doubtful. Also, property is divided into narrow lots with the houses on the streets and often little or no room between them to move a crane through. Property lines are defined by chain link fences, so you could not access the spots by crossing other's property by the seawall. Only the skid rig could be lifted over the seawall, so access to all four spots would be nessary. (2) A large track vehicle would still be needed to clear the boulder rip rap from the boring locations, but it is unlikely that any could be lifted over the breakwater. This would not be a problem if the crane had a clam shell; however, access to the wall would remain a problem for the crane.
January 9	<p>Friday: Ms. Dorothy Scholwin</p> <ul style="list-style-type: none"> - She would grant ATL an easement if the request is put in writing, the purpose of the easement and a description of the work included and sent to her VIA registered mail. She would then have her lawyer approve it. She stated that she did not feel opposed to our work; she was only trying to protect her own rights. (Her request was relayed to Canton, and a letter sent VIA Federal Express this afternoon. This letter is included in Section 9b).
January 13	<p>Tuesday: Yuri Yatsevitch</p> <ul style="list-style-type: none"> - Job progress: clearance of six borings by Ms. Scholwin, removal of rip rap at FD-0, desire to do all seaward borings this week.
January 20	<p>Tuesday: Yuri Yatsevitch</p> <ul style="list-style-type: none"> - Job progress. - Will be taking undisturbed samples tomorrow from 7:00 to 12:00.
January 21	<p>Wednesday: Terry Wong</p> <ul style="list-style-type: none"> - Job progress. - Plan to continue FD-0 tomorrow.

<u>Date</u>	<u>Conversation</u>
January 29	<p>Thursday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress. - Requested FD87-19 (FD-T) be terminated at 12' because it is in solid till yeilding bouncing refusal. Termination was granted. - Will move onto FD-0 today, have remainder of boulders cleared Tuesday. - Tide schedule will preclude work Friday and Monday.
February 2	<p>Monday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress.
February 3	<p>Tuesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Regarding early termination of FD87-15 (FD-0). Corps expects that we are drilling through a lense of sand and clay and that breakthrough should be within 10 ft. Material must have blow counts higher than 30/6" to be called till. - Undisturbed sampling method is acceptable.
February 4	<p>Wednesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress. - In FD87-15 (FD-0), we will take a split spoon from 45-47 ft. If it is clay, we will take a shelby tube from 47-49 ft. - Authorized us to continue the boring beyond 50 ft until we reached and verified till.
February 5	<p>Thursday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress and materials encountered. - Corps requested one final sample from 52 to 54 ft and then we could terminate the boring.
February 6	<p>Friday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress. - If we intersect 10 ft of till in boring FD-S or FD-U, may we terminate the boring? Yes. - A copy of the drilling logs has been requested by Carabetta Enterprises. Have them submit a formal application to the chief of the Engineering Division.
February 9	<p>Monday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Progress of job over weekend. - Requested and was given information on height of tides from the tide tables, which allowed us to schedule work for the remainder of the week and next week.
February 11	<p>Wednesday: Yuri Yatsevitch</p> <ul style="list-style-type: none"> - Re: delivery of samples tomorrow. Left message for Ron DeFilippo.

<u>Date</u>	<u>Conversation</u>
February 12	<p>Thursday: Yuri Yatsevitch, Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress. - Need the figure from the contract dictating specifications for an undisturbed sample shipping box. - Need copies of ENG Form 1743. - Need to locate first shipment of seven boxes.
February 13	<p>Friday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Job progress, soils encountered (woody organic material at base of shell-filled clay). - Would rely on the driller's expertise regarding the possibility of taking successful undisturbed samples. - Inspector will be Paul Fisher for the remainder of the job.
February 17	<p>Tuesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Project update. - Take split spoon samples if undisturbed sample tubes have no recovery in FD87-21.
February 18	<p>Wednesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Project update. - Requested FD87-21 (FD-Q) be extended past 50 ft if 30+ blow per 6" material is not achieved. - Sample on 10 ft increments or upon change in strata after 50 ft.
February 19	<p>Thursday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Project update. - Termination of FD87-21 (FD-Q) in dense sandy silt. - Samples will be delivered to Materials and Water Quality laboratory next week.
February 25	<p>Wednesday: Ron DeFilippo</p> <ul style="list-style-type: none"> - Must have someone from ATL inspect the replacement of the rip rap. Someone will come down from the Manchester, NH office. - Copies of the boring logs were not delivered with the samples. They will be mailed to his attention today.

SECTION 6

CHAIN OF CUSTODY LOGS



atl

ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG

PROJECT:

Roughan's Point, Revere MA
DACW 33-85-D-0011, D.O. #0018

ITEMS:

Tubes -0-
Bottles -0-
Jar Samples 7 boxes, 84 jars
Core Boxes -0-
Sampling Logs -0-

<u>Date & Time Received</u>	<u>Date & Time Transferred</u>	<u>Comments</u>	<u>Custodian</u>
as sampled	1/22/86 11:00		TB eddoe
1/22/86 11:00			RJ [signature]



atl ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG

PROJECT:

Roughan's Point, Duxbury MA
DACW 33-35-D-0011, D.O.# 0018

ITEMS:

Tubes 1
Bottles - 0 -
Jar Samples 4 boxes, 48 jars
Core Boxes - 0 -
Sampling Logs - 0 -

<u>Date & Time Received</u>	<u>Date & Time Transferred</u>	<u>Comments</u>	<u>Custodian</u>
<u>as sampled</u>	<u>2/12/87, 9:30</u>		<u>W. Beddoe</u>
<u>2/12/87, 9:30</u>			<u>Alexis M. Rainier</u>



atl

ATLANTIC TESTING LABORATORIES, Limited

Theresa Biddor

CHAIN OF CUSTODY LOG

PROJECT:

ROUGHAN'S POINT, REVERE BEACH, MA
DACW 33-85-D-0011, DO #0018

ITEMS:

3 Tubes FD-87-15 (UD-2) FD-87-21 (UD-1-2)

Bottles NONE

Jar Samples 3 Box FD-87-15, FD-87-21 & FD-87-22

Core Boxes NONE

Sampling Logs NONE

<u>Date & Time Received</u>	<u>Date & Time Transferred</u>	<u>Comments</u>	<u>Custodian</u>
<u>AS SAMPLED</u>	<u>2/21/87, 1200</u>	<u>PAUL FISHER</u>	<u>PRG</u>
<u>2/21/87, 1200</u>	<u>2/21/87, 1200</u>	<u>GREGORY P. CRAIG</u>	<u>GPC</u>
	<u>2/23/87 1030</u>	<u>JOSEPH COLUCCI</u>	<u>JCC</u>

SECTION 7

SAFETY REPORTS

WEEKLY SAFETY MEETING

NEDSO

Date held 12/30/81THRU: Area Engineer, New England AreaTime 12:00

TO: Safety Office, NED

Report No. C0020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Beedoe All personnel present (Contr) 4(Sub) 0(Govt) 0

Subjects discussed (Note, delete, or add):

EM 385-1-1, Section: _____

✓ Accident Prevention Plan

✓ Individual Protective Equipment - cold weather clothing, proper boots

✓ Prevention of Falls - use salt around equipment, watch footing along seawall

✓ Back Injury, Safe Lifting Techniques -

✓ Fire Prevention -

Sanitation, First Aid, Waste Disposal -

✓ Tripping Hazards - trash, hose, nails in lumber - place stored equipment properly

✓ Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

✓ Equipment Inspection & Maintenance (Zero Defects) - watch ropes and cables

✓ Hoisting Equipment -

✓ Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

✓ Loose Rock and Steep Slopes - seawall slopes and boulders

Explosives -

✓ Water Safety - re: tides

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other - delivered emergency phone #s

and hospital location to
drillersPrepared by TAB Title Geologist

12. Forwarded.

Signature Theresa A. Beedoe
Resident Engineer

CF: EXPOSURE HOURS:

Work Date: 12/29, 12/30, 12/31Non-work Date: 12/28, 1/1, 1/2, 1/3

NED, FL 251

Man Hours:

Contr: 52.5Subcontr: 0Govt: 0TOTAL: 52.5

WEEKLY SAFETY MEETING

NEDSO

Date held 1/6/87THRU: Area Engineer, New England AreaTime 2:30

TO: Safety Office, NED

Report No. ED020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.Conducted By TABeddoe All personnel present (Contr) 5
(Sub) 0
(Govt) 0Subjects discussed (Note, delete, or add):
EM 385-1-1, Section: _____

✓ Accident Prevention Plan

✓ Individual Protective Equipment - proper gloves

✓ Prevention of Falls - watch slick rocks - rocks icy in early morning

Back Injury, Safe Lifting Techniques -

✓ Fire Prevention -

✓ Sanitation, First Aid, Waste Disposal - no littering!

✓ Tripping Hazards - trash, hose, nails in lumber -

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

✓ Equipment Inspection & Maintenance (Zero Defects) - re: new gin ropes - will have them this weekend.

Hoisting Equipment -

✓ Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

✓ Loose Rock and Steep Slopes -

Explosives -

✓ Water Safety - watch the tides carefully for protection of personnel + equipment

Toxic materials - hazards, MSDS, respiratory, ventilation -

✓ Other - delivered emergency numbers to additional drillers

Prepared by Beddoe Title Geol.

2. Forwarded.

Signature Theresa A. Beddoe
Resident Engineer

CF: EXPOSURE HOURS:

Work Date: 1/5, 1/6, 1/7, 1/8, 1/9Non-work Date: 1/4, 1/10NED FL 251
APR 82

Man Hours:

Contr: 186Subcontr: 2Govt: 7TOTAL: 195

WEEKLY SAFETY MEETING

NEDSO

Date held 1/13/86

THRU: Area Engineer, New England Area

Time 7:00

TO: Safety Office, NED

Report No. 10020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.

Conducted By TABeddoe All personnel present (Contr) 5
(Sub) _____
(Govt) _____

Subjects discussed (Note, delete, or add):
EM 385-1-1, Section: _____

- ☒ Accident Prevention Plan
- ☒ Individual Protective Equipment -
- ☒ Prevention of Falls - watch footing at all times
- ☒ Back Injury, Safe Lifting Techniques -
- Fire Prevention -
- Sanitation, First Aid, Waste Disposal -
- ☒ Tripping Hazards - trash, hose, nails in lumber -
- Staging, Ladders, Concrete Forms, Safety Nets -
- Hand Tools, Portable Power Tools, Woodworking Machinery -
- ☒ Equipment Inspection & Maintenance (Zero Defects) -
- Hoisting Equipment -
- Ropes, Hooks, Chains and Slings -
- Electrical Grounding, Temporary Wiring, GFCI -
- Lockouts for safe clearance procedures - electrical, pressure, moving parts -
- Welding, Cutting -
- Excavations -
- ☒ Loose Rock and Steep Slopes -
- Explosives -
- ☒ Water Safety -
- Toxic materials - hazards, MSDS, respiratory, ventilation -
- Other -

Prepared by TABeddoe Title Geol.

2. Forwarded.

CF: EXPOSURE HOURS:

Work Date: 1/12, 1/13, 1/14
Non-work Date: 1/11, 1/15, 1/16, 1/17

NED FL 251
APR 82

Signature Theresa A. Beddoe
Resident Engineer

Man Hours:
Contr: 80
Subcontr: 4.5
Govt: 0
TOTAL: 84.5

WEEKLY SAFETY MEETING

NEDSO

Date held 1/20/86

THRU: Area Engineer, New England Area

Time 10:00

TO: Safety Office, NED

Report No. C0020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.

Conducted By Beddoe All personnel present (Contr) 5

(Sub) 0

(Govt) 0

Subjects discussed (Note, delete, or add):
EM 385-1-1, Section:

☒ Accident Prevention Plan

☒ Individual Protective Equipment -

☒ Prevention of Falls - watch ice!

Back Injury, Safe Lifting Techniques -

Fire Prevention -

Sanitation, First Aid, Waste Disposal -

☒ Tripping Hazards - trash, hose, nails in lumber - rocks

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

☒ Equipment Inspection & Maintenance (Zero Defects) -

Hoisting Equipment -

Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

☒ Loose Rock and Steep Slopes -

Explosives -

☒ Water Safety - moving rigs through water

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other -

Prepared by Beddoe Title Geol

2. Forwarded.

CF: EXPOSURE HOURS:

Work Date: 1/19, 1/20, 1/21, 1/22

Non-work Date: 1/18, 1/23, 1/24

NED FL 251
APP 62

Signature Theresa A. Beddoe
Resident Engineer

Man Hours:

Contr: 78.5

Subcontr: 0

Govt: 3.0

TOTAL: 81.5

WEEKLY SAFETY MEETING

NEDSO

Date held 1/27/87THRU: Area Engineer, New England AreaTime 12:00

TO: Safety Office, NED

Report No. 020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 18 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Reddoe All personnel present (Contr) 3

(Sub) _____

(Govt) _____

Subjects discussed (Note, delete, or add):

EM 385-1-1, Section: _____

☒ Accident Prevention Plan☒ Individual Protective Equipment - hard hats!☒ Prevention of Falls - watch footing on cobble slopes☒ Back Injury, Safe Lifting Techniques -

Fire Prevention -

Sanitation, First Aid, Waste Disposal -

☒ Tripping Hazards - trash, hose, nails in lumber -

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

☒ Equipment Inspection & Maintenance (Zero Defects) -☒ Hoisting Equipment -

Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

☒ Loose Rock and Steep Slopes -

Explosives -

Water Safety -

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other -

Prepared by Reddoe Title Geol.

2. Forwarded.

CF: EXPOSURE HOURS:

Work Date: 1/26, 1/27, 1/28, 1/29Non-work Date: 1/25, 1/30, 1/31NED FL 251
APR 82Signature Theresa A. Reddoe
Resident Engineer

Man Hours:

Contr: 57.5Subcontr: 0Govt: 0TOTAL: 57.5

WEEKLY SAFETY MEETING

NEDSO

Date held 2/3/87THRU: Area Engineer, New England AreaTime 11:00

TO: Safety Office, NED

Report No. C0020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Beddoe All personnel present (Contr) 3
(Sub) _____
(Govt) _____Subjects discussed (Note, delete, or add):
EM 385-1-1, Section: _____

Accident Prevention Plan

☒ Individual Protective Equipment - hard hats, steel toed shoes☒ Prevention of Falls -

Back Injury, Safe Lifting Techniques -

Fire Prevention -

☒ Sanitation, First Aid, Waste Disposal -☒ Tripping Hazards - trash, hose, nails in lumber - rocks!

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

☒ Equipment Inspection & Maintenance (Zero Defects) - like ALCOA

Hoisting Equipment -

Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

☒ Loose Rock and Steep Slopes - watch footing in rocks + gravel

Explosives -

☒ Water Safety -

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other -

Prepared by Beddoe Title Geol.

2. Forwarded.

Signature Herbert Beddoe
Resident Engineer

CF: EXPOSURE HOURS:

Work Date: 2/3, 2/4, 2/5, 2/6, 2/7Non-work Date: 2/1NED, FL 251
APR 82

Man Hours:

Contr: 102.0Subcontr: 7.5Govt: 2TOTAL: 111.5

WEEKLY SAFETY MEETING

NEDSO

Date held 2/9/87THRU: Area Engineer, New England AreaTime 12:00

TO: Safety Office, NED

Report No. 25030

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Beddoe All personnel present (Contr) 3
(Sub) -
(Govt) -Subjects discussed (Note, delete, or add):
EM 385-1-1, Section:

✓ Accident Prevention Plan

✓ Individual Protective Equipment -

✓ Prevention of Falls -

Back Injury, Safe Lifting Techniques -

Fire Prevention -

Sanitation, First Aid, Waste Disposal -

✓ Tripping Hazards - trash, hose, nails in lumber -

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

✓ Equipment Inspection & Maintenance (Zero Defects) -

✓ Hoisting Equipment -

✓ Ropes, Hooks, Chains and Slings - *gin rope will need replacing soon*

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

✓ Loose Rock and Steep Slopes -

Explosives -

✓ Water Safety - *make sure water shallow enough to allow rig to pass*Toxic materials - hazards, MSDS, respiratory, ventilation - *don't flood it*

Other -

Prepared by Beddoe Title Geol.

2. Forwarded.

CF: EXPOSURE HOURS:

Work Date: 2/8, 2/9, 2/10, 2/11, 2/12Non-work Date: 2/13, 2/14NED FL 251
APR 82Signature Theresa A. Beddoe
Resident Engineer

Man Hours:

Contr: 51.5Subcontr: 0Govt: 0TOTAL: 51.5

NEDSO

WEEKLY SAFETY MEETING

Date held 2/14/87

THRU: Area Engineer, NEW ENGLAND Area

Time 1700

TO: Safety Office, NED

Report No. CD020

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0018 Contractor Atlantic Testing Laboratories, Ltd.

Conducted By PAUL FISHER All personnel present (Contr) 3
(Sub) —
(Govt) —

Subjects discussed (Note, delete, or add):
EM 385-1-1, Section:

Accident Prevention Plan

- ✓ Individual Protective Equipment - BOOTS
- ✓ Prevention of Falls - RIP RAP, ICE
- ✓ Back Injury, Safe Lifting Techniques -
- Fire Prevention -
- Sanitation, First Aid, Waste Disposal -
- Tripping Hazards - trash, hose, nails in lumber -
- Staging, Ladders, Concrete Forms, Safety Nets -
- Hand Tools, Portable Power Tools, Woodworking Machinery -
- ✓ Equipment Inspection & Maintenance (Zero Defects) - MAINTENANCE OF RIG
- ✓ Hoisting Equipment - DRILL RIG
- ✓ Ropes, Hooks, Chains and Slings - CABLE
- Electrical Grounding, Temporary Wiring, GFCI -
- Lockouts for safe clearance procedures - electrical, pressure, moving parts -
- Welding, Cutting -
- Excavations -
- ✓ Loose Rock and Steep Slopes - RIP RAP
- Explosives -
- ✓ Water Safety - OCEAN
- Toxic materials - hazards, MSDS, respiratory, ventilation -
- Other -

2. Forwarded.

Prepared by P. FISHER Title ENG

Signature [Signature]
Resident Engineer

CF: EXPOSURE HOURS:

Work Date: 2/16, 2/17, 2/18, 2/19

Non-work Date: 2/15, 2/20, 2/21

NED FL 251
APP 82

Man Hours:

Contr: 58 1/2

Subcontr: 6 1/2


Govt: 0

TOTAL: 65

a. Figure 1 - General Project Map

FIGURE 1

GENERAL PROJECT MAP



PROJECT SITE

MASSACHUSETTS

□ BAY
Graves Lighthouse

BOSTON

SUFFOLK

Quincy

Weymouth

NORFOLK

Stoughton

Abington

MASSACHUSETTS


PROJECT No. CD020

SCALE: 1 in. = 7 mi.

b. Figure 2 – Site Location Map

FIGURE 2

SITE LOCATION MAP




PROJECT No CD020

SCALE: 1:25,000

U.S.G.S. QUAD: Boston North and Lynn
Massachusetts

c. Figure 3 – Boring Location Plan



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O. #0018

Site Roughan's Point, Duxbury MA

Page 1 of 4 Pages

Hole No. ED86-1 Dim. (Casing) 3 1/4" Hollow Stem Auger

Boring Started 12/31/86

Co-ordinates: X see X sketch

Boring Completed 12/31/86

Drilled by Todd E Saoninen

Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms.

Elevation Top of Hole 9.80 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 15.0 Feet

Elevation Top of Rock — M.S.L.

Elevation Bottom of Hole -5.2 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 15.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; — Diam. — In.

Soil Samples 1 3/8 In. Diam. 5 No.

Soil Samples — In. Diam. — No.

Water Table Depth 8.6'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger *
13.0	15.0	1 3/8" ID Split Spoon Sampler
		* with 1 3/8" split spoon sampling every 5'.

INDEX

Ground Water Back of Page 4
Boring Location Sketch Back of Page 4
Overburden Record Page 2-3
Rock Drilling Page
Page
Page
Page

Prepared by TAB-ldoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughans Pt, Revere MA Page 2 of 4 Pages

Boring No. FD86-1 Desig. V Diam. (Casing) 3 1/4" ^{Hollow} Stem
Auger

Co-ordinates: N see & sketch

FIELD LOG OF TEST BORING

Elevation Top of Boring 9.80 M.S.L. Hammer Wt. 140[#] Boring Started 12/31/86
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0 Boring Completed 12/31/86
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -5.2 M.S.L. Obs. Well no
Total Depth of Boring 15.0 Feet Drilled By Todd J. Saarinen
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill skid-mounted CHE 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoe
Soil Samples 1 3/8 In. Diam. 5 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
0.0'	1" 2'	NO.	SIZE	DEPTH RANGE			
				REL	3	Sample using 1 3/8" ID by 2' long split spoon sampler	Dark brown m & SAND and
		5-1	1 3/8"	15%	4		& GRAVEL, little SILT, trace
					8		
2.0'					9		
						3 1/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring	medium dense <u>SP-FILL</u>
5.0'							Note softer drilling consistency at 4.0'
					5	Sample as above.	Medium grey & SAND
		5-2	1 3/8"	20%	7		and SILT, trace &
					8		
7.0'					11		GRAVEL, trace CLAY
						Auger to 10'	(moist, very slightly plastic) medium dense <u>SM</u>
10.0'							

GENERAL REMARKS:

Elevations as surveyed in the field by ATL using
benchmark near FD-5 (FD87-20)

All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH		CORE/SAMPLE		SLOW SAMPLING		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0	1.21	NO	SIZE	REL	CORE RECOVERY		
11.0		S-3A	1 3/8"	80%	19 24	Sample using 1 3/8" ID by 2' long split spoon sampler	Soils similar to S-2, no CLAY - <u>SM</u>
12.0		S-3B	1 3/8"	80%	25 30	3/4" Hollow Stem Auger to 13.0'	Medium brown cml SAND
13.0							trace of GRAVEL, trace SILT
14.0					23 17 19 20	Sample as above	(saturated, non plastic) very dense <u>SW</u>
15.0		S-4	1 3/8"	40%			Soils similar to S-3B with a 1" plug of soils similar to S-3A <u>SW</u>
						Boring Terminated at 15.0', 12/31/86.	

Site: Roughams Point, Revere MA
Boring No: FD86-1


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Not to Scale



59 (Test)

Boring No. FA86-1

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O. #0018

Site Roughan's Point, Revere MA

Page 1 of 4 Pages

Hole No. ED87-1 Dim. (Casing) 3 1/4" Hollow Stem
Auger

Boring Started 1/6/87

Co-ordinates: X see & sketch

Boring Completed 1/6/87

Drilled by Todd + Saarinen

Report Submitted

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth beams

Elevation Top of Hole 1.30 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 25.0 Feet

Elevation Top of Rock — M.S.L.

Elevation Bottom of Hole -23.7 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 25.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; — Dim. — In.

Soil Samples 1 3/8 In. Dim. 6 No.

Soil Samples — In. Dim. — No.

Water Table Depth 5.0'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	23.0	3 1/4" ID Hollow Stem Auger *
23.0	25.0	1 3/8" ID Split Spoon Sampler
		* with 1 3/8" ID Split Spoon Sampling every 5'.

INDEX

Ground Water	Back of Page <u>4</u>
Boring Location Sketch	Back of Page <u>4</u>
Overburden Record	Page <u>2-3</u>
Rock Drilling	Page
	Page
	Page
	Page

Prepared by TJ Beddoe

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughan's Point, Revere MA Page 2 of 4 Pages

Boring No. ED87-1 Desig. F Diam. (Casing) 3 1/4" Hollow Stem Auger

FIELD LOG OF TEST BORING

Co-ordinates: X see X sketch

Elevation Top of Boring 1.30 M.S.L. Hammer Wt. 140 lbs Boring Started 1/6/87
Total Overburden Drilled 25.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/6/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -23.7 M.S.L. Obs. Well no
Total Depth of Boring 25.0 Feet Drilled By Todd + Saarinen
Core Recovered 0% No. Boxes 0 Mfg. Des. Drill skid mounted CHE45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoe
Soil Samples 1 3/8 In. Diam. 6 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FEET CORE RECOVERED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" 2'	NO.	SIZE			
2.0		S-1	1 3/8"	25%	Sample using 1 3/8" ID by 2' long split spoon sampler	Med. brown cf GRAVEL, some cmf SAND, trace SILT, trace DEBRIS (glass shell fragments) (saturated, nonplastic) dense <u>GW</u>
5.0					3/4" ID Hollow Stem Auger to 5.0'. Augering easy throughout boring.	
7.0		S-2	1 3/8"	17%	Sample as above	Med. brown cf GRAVEL and cmf SAND, trace SILT (saturated, nonplas- tic) with two lenses of medium brown & SAND and SILT, little CLAY (saturated, slightly plastic)
10.0					Auger to 10.0'	loose <u>GP</u>

GENERAL REMARKS:

Elevations as surveyed in the field by
ATL using benchmark near ED-S (ED87-30).
All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH 10.0	1" 2'	CORE/SAMPLE		BLOW COUNT REMARKS	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
		NO	SIZE			
10.0		S-3	1 3/8"	REC 75%	Sample using 1 3/8" ID by 2' long split spoon sampler.	Med. grey-brown CLAY and SILT, trace of SAND, trace of GRAVEL (saturated, plastic) hard <u>CL</u>
12.0					3/4" ID Hollow Stem Auger to 15.0'	
15.0		S-4	1 3/8"	100%	sample. as above	Med grey med SAND and of GRAVEL, trace SILT (sat., nonplastic) with one layer of soil similar to S-3 medium dense <u>SW</u>
17.0					Auger to 20.0'	
20.0		S-5	1 3/8"	100%	Sample as above	Med grey med SAND, trace of GRAVEL, trace SILT (sat., nonplastic) medium dense <u>SP</u>
22.0					Auger to 23.0'	
23.0		S-6	1 3/8"	100%	Sample as above	Very dense Similar Soils - <u>SP</u>
25.0					Boring Terminated at 25.0', 1/6/87.	

Site: Roughan's Point

Boring No: FD 87-1


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Not to Scale



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O. # 0018

Site Rougham's Point, Revere M.A.

Page 1 of 4 Pages

Hole No. ED87-2 Dim. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~

Boring Started 1/6/87

Co-ordinates: X see X Sketch

Boring Completed 1/6/87

Drilled by Cambridge + Mordock

Report Submitted

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms.

Elevation Top of Hole 0.00 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 15.0 Feet

Elevation Top of Rock — M.S.L.

Elevation Bottom of Hole -15.0 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 15.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; — Dim. — In.

Soil Samples 1 3/8 In. Dim. 4 No.

Soil Samples — In. Dim. — No.

Water Table Depth 3.7'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger*
13.0	15.0	1 3/8" ID Split Spoon Sampler
		*with 1 3/8" ID split spoon sampling every 5'

INDEX

Ground Water Back of Page 4
Boring Location Sketch Back of Page 4
Overburden Record Page 2-3
Rock Drilling Page
Page
Page
Page

Prepared by TABeddoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughan's Point, Revere MA Page 2 of 4 Pages
Boring No. FD87-2 Desig. E Diam. (Casing) 3 1/4" ^{Hollow} _{Auger} Stem
Co-ordinates: X see sketch X

FIELD LOG OF TEST BORING

Elevation Top of Boring 0.00 M.S.L. Hammer Wt. 140# Boring Started 1-6-87
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left no Boring Completed 1-6-87
Total Rock Drilled 0 Feet Subsurface Water Date — Page 4
Elevation Bottom of Boring -15.0 M.S.L. Obs. Well no
Total Depth of Boring 15.0 Feet Drilled By Cambridge + Hurdock
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill Hack mounted CME45
Core Recovered 0 Ft. : — Diam. — In. Inspected By: Beddoe
Soil Samples 1 3/8 In. Diam. 4 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORRECTION	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" = 2'	NO.	SIZE	DEPTH RANGE		
0.0				REC	19	Med. brown & GRAVEL and CME SAND, trace SHELL FRAGMENTS, trace SILT (saturated, nonplastic) dense <u>GW</u>
		5-1	1 3/8"	20%	16	
					17	
2.0'					21	
						Med. grey SILT, some SAND, some CLAY, trace of GRAVEL (sat., mod. plastic) medium stiff <u>MH</u>
					2	
		5-2	1 3/8"	25%	3	
					3	
7.0					3	Auger to 10.0'
10.0						

GENERAL REMARKS:

Elevations as surveyed in the field by
ATL using benchmark near FD-5 (FD87-20).
All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH		CORE/SAMPLE		BLOW COUNT		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	1" 2'	NO.	SIZE	FEET	PERCENT		
				REL	18	Sample using 1 3/8" ID by 2' long split spoon sampler.	MH as above
					7		
		S-3	1 3/8"	100%	3		
					9		
12.0						3/4" ID Hollow Stem Auger to 13.0'	
13.0							
					8	Sample as above	Md. grey cnp SAND and cP GRAVEL, little SILT, trace CLAY (sat., very slightly plastic) medium dense <u>SP-SM</u>
					8		
		S-4	1 3/8"	75%	8		
					11		
15.0						Boring Terminated at 15.0' 1/6/87.	

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughans Point, Revere MA PROJECT NO. D.O. # 0018
Page 1 of 4 Pages
Hole No. FD37-3 Diam. (Casing) 3 1/4" ID Hollow Stem Auger Boring Started 1/6/87
Co-ordinates: X see X sketch Boring Completed 1/6/87
Drilled by Todd + Saarinen Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate, and earth beams

Elevation Top of Hole 7.70 M.S.L.
Total Overburden Drilled 15.0 Feet
Elevation Top of Rock — M.S.L.
Elevation Bottom of Hole -7.30 M.S.L.
Total Rock Drilled 0 Feet
Total Depth of Hole 15.0 Feet
Core Recovered 0 %
Core Recovered 0 Ft.; — Diam. — In.
Soil Samples 1 3/8 In. Diam. 4 No.
Soil Samples — In. Diam. — No.

Casing Left in Place 0 Feet

Water Table Depth 7.0'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger *
13.0	15.0	1 3/8" ID Split Spoon Sampler
		*with 1 3/8" ID Split Spoon Sampling every 5'

INDEX

Ground Water _____ Back of Page 4
Boring Location Sketch _____ Back of Page 4
Overburden Record _____ Page 2-3
Rock Drilling _____ Page _____
_____ Page _____
_____ Page _____
_____ Page _____

Prepared by TABedoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

FIELD LOG OF TEST BORING

Co-ordinates: N see sketch E

Elevation Top of Boring 7.70 M.S.L. Hammer Wt. 140 # Boring Started 1-6-87
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1-6-87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -7.30 M.S.L. Obs. Well no
Total Depth of Boring 15.0 Feet Drilled By Todd + Saarinen
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill skid-mounted CME45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddor
Soil Samples 1 3/8 In. Diam. 4 No. Classification By: Beddor
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" 2'	NO.	SIZE	DEPTH RANGE		
0.0				REC	2	Med. brown cmf SAND, little F GRAVEL, trace SHELL FRAGMENTS, trace
					3	
		S-1	1 3/8"	40%	4	
					12	
2.0						3 1/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring.
5.0					10	Similar Soils (with one 1/2" layer Med. grey SILT, some mf SAND, some CLAY (sat., mod. pl.) (saturated, nonplastic) medium dense SW
					12	
		S-2	1 3/8"	50%	15	
					18	
7.0						Auger to 10.0'. medium dense SW
10.0						

GENERAL REMARKS:

Elevations as surveyed in the field by
ATL using benchmark FD-3 (FD87-20).
All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH		CORE/SAMPLE		BLOW COUNT		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	1" 2'	NO	SIZE	REV	REV		
10.0							
				REC	3	Sample using 1 3/8" ID by 2' long split spoon sampler.	SW as above (no sample retained)
		S-3	1 3/8"	50%	3		
					2		
					3		
12.0						3/4" ID Hollow Stem Auger to 13.0'	Med grey SILT and CLAY, trace ORGANICS (roots, etc), trace F. SAND, trace F GRAVEL (wet, plastic)
13.0							
					14	Sample as above	medium stiff <u>MH</u> Note natural sulphur odor. "PEAT" Dark grey & GRAVEL and cm F SAND, trace SILT (saturated, nonplastic) medium dense <u>GL</u>
		S-4	1 3/8"	50%	9		
					12		
					9		
15.0						Boring terminated at 15.0' 1/6/87.	

Site: Roughans Point

Boring No: FD87-3


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Not to Scale



Note: As-built boring location is the requested location.

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. B.O. #0018
 Hole No. ED87-4 Dim. (Casing) 3 1/4" Hollow Stem Auger Page 1 of 4 Pages
 Co-ordinates: X see sketch Boring Started 1/6/86
 Drilled by Cambridge + Murdock Boring Completed 1/6/86
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms

Elevation Top of Hole 11.70 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 25.0 Feet
 Elevation Top of Rock — M.S.L.
 Elevation Bottom of Hole -13.30 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 25.0 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.; — Dim. — In.
 Soil Samples 1 3/8 In. Diam. 6 No.
 Soil Samples — In. Diam. — No. Water Table Depth 2.0'

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0.0	23.0	3 1/4" ID Hollow Stem Auger *	Ground Water	Sketch of Page <u>4</u>
23.0	25.0	1 3/8" ID Split Spoon Sampler	Boring Location Sketch	Sketch of Page <u>4</u>
		* with 1 3/8" ID Split Spoon Sampling every 5'	Overburden Record	Page <u>2-3</u>
			Rock Drilling	Page _____
				Page _____
				Page _____

Prepared by T. Beddoe Field Data
 Submitted by Atlantic Testing Labs, Ltd. Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Boughans Point, Revere MA Page 2 of 4 Pages

Boring No. FD87-4 Desig. D Diam. (Casing) 3 1/4" Hollow Stem Auger

FIELD LOG OF TEST BORING

Co-ordinates: X see sketch 8

Elevation Top of Boring 11.70 M.S.L. Hammer Wt. 140# Boring Started 1/6/87
Total Overburden Drilled 25.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/6/87
Total Rock Drilled 0 Feet | Subsurface Water Data — | Page 4
Elevation Bottom of Boring -13.3 M.S.L. | Obs. Well no
Total Depth of Boring 25.0 Feet Drilled By Cambridge + Murdock
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddop
Soil Samples 13/8 In. Diam. 6 No. Classification By: Beddop
Soil Samples — In. Diam. — No. Classification By: —


DEPTH		CORE/SAMPLE		BLOWS PER FT CORE READY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" = 2'	NO.	SIZE			
0.0'				REC	Sample using 1 3/8" ID by 2' long split spoon sampler	Light brown f SAND, trace ORGANICS (roots, grass), trace f GRAVEL, trace SILT (moist, nonplastic) loose SP
		5-1	1 3/8"	50%		
				4		
				5		
2.0'				7	2 1/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring	Med. brown mf SAND, little f GRAVEL, trace SILT (moist, nonplastic) medium dense SP
5.0'					Sample as above	
		5-2	1 3/8"	75%		
				13		
				10		
				8	Auger to 10.0'	
				7		
7.0'						
10.0'						

GENERAL REMARKS:

Elevations as surveyed in the field by
ATL using benchmark near FD-S (FD87-20).
All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH		COLE/SAMPLE		BLOW COUNT PER FOOT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0	1.21	NO	SIZE			
10.0		S-3	1 3/8"	100%	8 2 2 1 Sample using 1 3/8" ID by 2' long split spoon sampler.	Dark brown SILT, little ORGANIC MATERIAL (grass, roots, worms) Trace CLAY, trace F SAND
12.0					3 1/4" ID Hollow Stem Auger to 15.0'	(moist, very slightly plastic) soft <u>OL</u> "PEAT" Note sulphur odor. (natural)
15.0		S-4	1 3/8"	80%	4 4 9 12 Sample as above	Dark brown F SAND, some SILT, little CLAY, trace c GRAVEL (wet, slightly plastic) medium dense <u>SM</u>
17.0					Auger to 20.0'	
20.0		S-5	1 3/8"	100%	4 9 14 12 Sample as above	Dark grey SILT, some CLAY, little F SAND (saturated, moderately plastic) very stiff
22.0					Auger to 23.0'	<u>M.H</u> Note sulphur odor. (natural).
23.0					Sample as above	Dark brown cml SAND and c GRAVEL, little SILT, trace CLAY (sat., very
25.0		S-6	1 3/8"	100%	15 13 10 10	slightly plastic) medium dense <u>SW</u>
					Boring Terminated at 25.0' 11/6/87.	

Note: Depths are in feet below original ground

BORING LOCATION SKETCH *Not to Scale*

Note: As-built boring location is the requested location.

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughans Point, Revere MA PROJECT NO. D.O.#0018
Page 1 of 4 Pages

Hole No. FD87-S Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 1/6/86

Co-ordinates: X see X sketch Boring Completed 1/6/86

Drilled by Cambridge & Muddock Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms.

Elevation Top of Hole 9.90 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 15.0 Feet

Elevation Top of Rock — M.S.L.

Elevation Bottom of Hole -5.1 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 15.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; — Diam. — In.

Soil Samples 13/8 In. Diam. 4 No.

Soil Samples — In. Diam. — No.

Water Table Depth 5.25'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger *
13.0	15.0	1 3/8" ID Split Spoon Sampler
		* with 1 3/8" ID split spoon sampling every 5'

INDEX

Ground Water _____ Back of Page 4
Boring Location Sketch _____ Back of Page 4
Overburden Record _____ Page 2-3
Rock Drilling _____ Page _____
_____ Page _____
_____ Page _____
_____ Page _____

Prepared by TABeddoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughans Point, Revere MA Page 9 of 4 Pages

Boring No. FD87-5 Desig. A Diam. (Casing) 3 1/4" Hollow Stem Auger

FIELD LOG OF TEST BORING

Co-ordinates: N see sketch R

Elevation Top of Boring 7.90 M.S.L. Hammer Wt. 140# Boring Started 1/6/87
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/6/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -5.1 M.S.L. Obs. Well ND
Total Depth of Boring 15.0 Feet Drilled By Cambridge + Muddock
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddor
Soil Samples 1 3/8 In. Diam. 4 No. Classification By: Beddor
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. COTE RANGE RECVY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" = 2'	NO.	SIZE			
0.0				3	Sample using 1 3/8" ID by 2' long split spoon sample.	Light brown m ^{lt} SAND, little & GRAVEL, trace SILT (moist, nonplastic)
				5		
				9		
				11		
2.0					3/4" Hollow Stem Auger to 5.0' Augering easy throughout boring.	medium dense <u>SP</u>
5.0					Sample as above	Med. brown cmf SAND, some cf GRAVEL, trace SILT (wet, nonplastic)
				12		
				14		
				19		
7.0				31	Auger to 10.0'	dense <u>SW</u>
10.0						

GENERAL REMARKS:


Elevations as surveyed in the field by ATL
using benchmark near FD-S, (FD87-20)
All soil sampling performed in accordance with ASTM
D1586 except as noted.

Boring No. FD87-5

DEPTH	CORRECTION	CORRECTION	CORRECTION	CORRECTION	CORRECTION	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0	1.0	2'	NO	SIZE	PERCENT		
						Sample using 1 3/8" ID by 2' long split spoon sampler.	Dark brown SILT and CLAY, trace of GRAVEL, trace of SAND, trace ORGANICS
12.0						3 1/4" ID Hollow Stem Auger to 13.0'	(grass) (saturated, plastic)
13.0						Sample as above	soft + <u>MH</u> Note natural sulphur odor
15.0						Boring Terminated at 15.0' 1/6/87	Dark brown SILT and CLAY, little ORGANICS (grass, roots, worms), trace of SAND (wet, plastic) very stiff <u>MH</u> "PEAT" Note natural sulphur odor
							Note change @ 14.9 to SW sands - no sample retained as inspector was at other drill rig. Material composition substantiated by driller.

[illegible]

Note: Depths are in feet below original ground



Note: As-built boring location is the requested location.

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughans Point, Revere MA PROJECT NO. D.O. #0016
Page 1 of 4 Pages

Hole No. FD87-6 Diam. (Casing) 3 1/4" ID Hollow Stem Auger Boring Started 1/6/87

Co-ordinates: X see X sketch Boring Completed 1/6/87

Drilled by Todd + Saatinen Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed revetments, sluice gate and earth berms.

Elevation Top of Hole 12.00 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 25.00 Feet

Elevation Top of Rock — M.S.L.

Elevation Bottom of Hole -13.00 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 25.00 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; — Diam. — In.

Soil Samples 1 3/8 In. Diam. 6 No.

Soil Samples — In. Diam. — No.

Water Table Depth 13.0'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	23.0	3 1/4" ID Hollow Stem Auger *
23.0	25.0	1 3/8" ID Split Spoon Sampler
		* with 1 3/8" ID Split Spoon Sampling on 5' intervals

INDEX

Ground Water _____ Back of Page 4
Boring Location Sketch _____ Back of Page 4
Overburden Record _____ Page 2-3
Rock Drilling _____ Page _____
_____ Page _____
_____ Page _____
_____ Page _____

Prepared by J. A. Seddore Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughams Point, Revere MA Page 8 of 4 Pages

Boring No. FD87-6 Desig. B Diam. (Casing) 3/4" Hollow Stem Auger

Co-ordinates: None sketch R

FIELD LOG OF TEST BORING

Elevation Top of Boring 12.00 M.S.L. Hammer Wt. 140 # Boring Started 1/6/87
Total Overburden Drilled 25.00 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/6/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -13.00 M.S.L. Obs. Well no
Total Depth of Boring 25.00 Feet Drilled By Todd + SaaHnen
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CHF 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoo
Soil Samples 1 3/8 In. Diam. 6 No. Classification By: Beddoo
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
1" 2'	NO.	SIZE	DEPTH RANGE	CORE RECVY		
2.0				REL	1	light brown f SAND, trace G GRAVEL, trace SILT (moist, nonplastic) medium dense <u>SP</u>
	5-1	1 3/8"	50%		6	
					11	
2.0					11	
						3/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring
5.0						
	5-2	1 3/8"	40%		3	similar soils - SP - with 3" layer of dark grey CLAY and SILT, trace f. SAND (wet, plastic) medium stiff <u>CL</u>
					2	
					3	
7.0					4	
						Auger to 10.0'
10.0						

GENERAL REMARKS:

Elevations as surveyed in the field by
ATL using benchmark near FD-5. (FD87-20).
All soil sampling performed in accordance with ASTM
D1586 except as noted.


Boring No. FD87-6

DEPTH		CORE/SAMPLE		BLOW COUNT PER FOOT CORE RECY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0	1.2	NO.	SIZE			
10.0		S-3	1 3/8"	75% REC	7 3 2 3 Sample using 1 3/8" ID by 2' long split spoon sampler	SP as above no sample retained Dark brown CLAY and SILT, little ORGANICS roots, grass, trace F. SANDS (wet, plastic) ^{medium} STIFF CL Note natural sulphur odor "PEAT"
15.0					3/4" Hollow Stem Auger to 15'	
17.0		S-4	1 3/8"	45%	5 6 9 9 Sample as above	Dark brown mf SAND, some cf GRAVEL, trace SILT, trace CLAY (saturated, very slightly plastic) medium dense SP
20.0					Auger to 20'	
22.0		S-5	1 3/8"	45%	17 13 11 13 Sample as above	Dark brown cmf SAND and cf GRAVEL, trace SILT, trace CLAY (sat, very slightly plastic) medium dense SW
23.0					Auger to 23.0'	
25.0		S-6	1 3/8"	75%	15 16 15 12 Sample as above	Similar soils with <u>no</u> CLAY - <u>SW</u>
					Boring Terminated at 25.0' 11/6/86	

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH *Not to Scale*



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughans Point, Revere MA PROJECT NO. D.O. #0018
Page 1 of 4 Pages

Hole No. FD87-7 Diam. (Casing) 3/4" ID ~~Hollow Stem~~ Auger Boring Started 1/7/87

Co-ordinates: X sec X sketch Boring Completed 1/7/87

Drilled by Todd + Saarinen Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth beams

Elevation Top of Hole -1.60 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 15.0 Feet

Elevation Top of Rock — M.S.L.

Elevation Bottom of Hole -14.6 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 15.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; — Diam. — In.

Soil Samples 13/8 In. Diam. 5 No.

Soil Samples — In. Diam. — No.

Water Table Depth surface

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3/4" ID Hollow Stem Auger with 1 3/8" ID split spoon sampling on 5' intervals
13.0	15.0	1 3/8" ID split spoon sampler

INDEX

Ground Water Back of Page 4
Boring Location Sketch Back of Page 4
Overburden Record Page 2-3
~~Rock Drilling~~ Page
Page
Page
Page

Prepared by TJ Beddoe

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughans Point, Revere MA Page 2 of 4 Pages
Boring No. FD87-7 Desig. G Diam. (Casing) 3 1/4" ID ^{Hollow Stem Auger}
Co-ordinates: see sketch

FIELD LOG OF TEST BORING

Elevation Top of Boring -1.40 M.S.L. Hammer Wt. 140# Boring Started 1/7/87
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/7/87
Total Rock Drilled 0 Feet (Subsurface Water Data — Page 4)
Elevation Bottom of Boring -16.4 M.S.L. Obs. Well no
Total Depth of Boring 15.0 Feet Drilled By Todd + Sothman
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft. — Diam. — In. Inspected By: Beddoe
Soil Samples 13/8 In. Diam. 5 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1'-2'	NO.	SIZE	DEPTH RANGE RECVY		
				REC	11 Sample using 1 3/8" ID by 2' long split spoon sampler	Medium brown CF GRAVEL, some mf. SAND, trace SHELL FRAGMENTS, trace SILT (saturated, nonplastic) medium dense <u>GW</u>
		5-1	1 3/8"	25%	13 16 8	
2.0'					3 1/4" ID Hollow Stem Auger to 5.0'; Augering easy throughout boring.	
5.0'					34 Sample as above	Dark grey <u>GW</u> as above
		5-2	1 3/8"	50%	17 12 11	
7.0'						
					Auger to 10.0'	
10.0'						

GENERAL REMARKS:

Elevations as surveyed in the field by ATL
using benchmark near FD-S. (FD87-20)
All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH		CORE/SAMPLE		BLOW COUNT PER FOOT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	1.0'	NO	SIZE			
10.5'		S-3A	1 3/8"	100%	34	Dark grey mf SAND, trace SILT, trace SHELL FRAGMENTS (saturated, non-plastic) ^{very} dense SP
		S-3B	1 3/8"	100%	15 8	
12.0'					9	Dark grey cmf SAND and f GRAVEL, trace SILT (saturated, non- plastic) ^{medium} dense SW
13.0'						
		S-4	1 3/8"	100%	56 24 29 31	Med. grey cf GRAVEL and cmf SAND, trace
15.0'						
						Boring Terminated at 15.0', 11/1/87

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. # 0018
 Hole No. FD27-2 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Page 1 of 4 Pages
 Co-ordinates: X see sketch Boring Started 1/7/87
 Drilled by Cambridge & Murdock Boring Completed 1/7/87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms

Elevation Top of Hole 0.80 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 25.0 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole -24.2 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 25.0 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.; _____ Dim. _____ In.
 Soil Samples 1 3/8 In. Diam. 7 No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth 0.5'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	33.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling on 5' intervals.
23.0	25.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water _____	Back of Page <u>4</u>
Boring Location Sketch _____	Back of Page <u>4</u>
Overburden Record _____	Page <u>2-3</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by TA Beddoe Field Data
 Submitted by Atlantic Testing Labs, Ltd. Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Doughan's Point, Penne MA Page 2 of 4 Pages

Boring No. FD87-8 Desig. H Diam. (Casing) 3 1/4" ID ^{Hollow stem Auger}

FIELD LOG OF TEST BORING

Co-ordinates: X see sketch R

Elevation Top of Boring 0.80 M.S.L. Hammer Wt. 140 # Boring Started 1/7/87
Total Overburden Drilled 25.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/7/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -24.2 M.S.L. Obs. Well no
Total Depth of Boring 25.0 Feet Drilled By Cambridge + Mudack
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CHE 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddor
Soil Samples 1 3/8 In. Diam. 7 No. Classification By: Beddor
Soil Samples — In. Diam. — No. Classification By: —

DEPTH	CORE/SAMPLE		BLOWS PER FT. CORRECTION	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE			
0.0'					
1.0'					
2.0'	S-1	1 3/8"	30%	Sample using 1 3/8" ID by 2' long split spoon sampler	Red brown cme SAND and GRAVEL, trace SHELL FRAGMENTS, trace SILT
3.0'				3/4" ID Hollow stem auger to 5'.	(saturated, nonplastic) dense SW
4.0'				Note boulders in first 5.0'.	
5.0'					
6.0'	S-2A	1 3/8"	100%	Sample as above	Dark brown SILT and CLAY, trace SAND,
7.0'	S-2B	1 3/8"	100%		trace ORGANICS (roots), trace GRAVEL (saturated, plastic) stiff MH
8.0'					"PEAT" note sulphur odor. (natural).
9.0'					Medium brown mf SAND,
10.0'					trace GRAVEL, trace SILT (saturated, nonplastic) medium dense SP
<p>GENERAL REMARKS: Elevations as surveyed in the field by ATL using benchmark near FD-S. (FD87-20). All soil sampling performed in accordance with ASTM D1586 except as noted.</p>					

Boring No. FD87-8

5118		Roughan's Point				Boring No. FD87-8		Page 3 of 4	
DEPTH		CORE/SAMPLE		BLOWS		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS	
10.0'	2'	NO	SIZE	REC	STANDARD PENETRATION TEST				
		S-3	1 3/8"	50%	5 7 13 10	Sample using 1 3/8" ID by 2' long split spoon sampler		Soils Similar to S-2B - <u>SP</u>	
12.0'						3/4" ID Hollow Stem Auger to 15.0'			
		S-4	1 3/8"	50%	14 12 6 5	sample as above		Dark brown & SAND, little SILT, trace < GRAVEL, trace CLAY, trace ORGANICS (roots)	
17.0'						Auger to 20.0'		(saturated, very slightly plastic) medium dense <u>SP-SM</u> Note sulphur odor. (natural).	
20.0		S-5	1 3/8"	60%	3 8 8 9	sample as above		<u>SP-SM</u> as above	
22.0						Auger to 23.0'			
23.0						sample as above		Med. grey-brown mf SAND trace & GRAVEL, trace SILT (saturated, nonplastic) dense <u>SP</u>	
25.0		S-6	1 3/8"	100%	8 12 20 21	Boring Terminated at 25.0' 11/7/87			

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. B.O. #0018
 Hole No. FD87-9 Diam. (Casing) 3 1/4" ID Hollow Stem Auger Page 1 of 4 Pages
 Co-ordinates: X see X sketch Boring Started 1/7/87
 Drilled by Todd & Saarinen Boring Completed 1/7/87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berm.

Elevation Top of Hole -1.5 M.S.L.
 Total Overburden Drilled 15.0 Feet
 Elevation Top of Rock — M.S.L.
 Elevation Bottom of Hole -13.5 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 15.0 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.; — Diam. — In.
 Soil Samples 13/8 In. Diam. 6 No.
 Soil Samples — In. Diam. — No.

Casing Left in Place 0 Feet

Water Table Depth surface

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling on 5' intervals
13.0	15.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water	<u>Back of Page 4</u>
Boring Location Sketch	<u>Back of Page 4</u>
Overburden Record	Page <u>2</u>
Rock Drilling	Page _____
	Page _____
	Page _____
	Page _____

Prepared by T A Beddoe

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd

FIELD LOG OF TEST BORING

Co-ordinates: see sketch

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" 2'	NO.	SIZE	DEPTH RANGE		
0.0	1" 2'					
2.0		S-1	1 3/8"	40%	4 13 12 9	Sample using 1 3/8" ID by 2' long split spoon sampler
5.0						Med. brown <u>CE</u> GRAVEL and fine SAND, trace SILT, trace SHELL FRAGMENTS (saturated, nonplastic) medium dense <u>GW</u>
7.0		S-2	1 3/8"	35%	14 16 19 14	2 1/4" ID Hollow Stem Auger to 5.0' Augering slightly difficult due to coarse soils
10.0						Sample as above Light rust-brown <u>GW</u> as above
						Auger to 10.0' Augering easy for remainder of boring.

58 (Test)

Boring No. ED87-9

DEPTH		CORE/SAMPLE		BLOWS PER FEET CORRECTED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	12'	NO.	SIZE			
				REC	Sample using 1 3/8" ID by 2' long split spoon sampler	Light brown cmf SAND, trace of GRAVEL, trace SILT (wet, nonplastic) very dense <u>SP</u>
11.5'		S-3A	1 3/8"	100%		Light brown of SAND, trace of GRAVEL, trace SILT (wet, nonplastic) very dense <u>SP</u>
12.0'		S-3B	1 3/8"	100%		Light brown of SAND, trace of GRAVEL, trace SILT (wet, nonplastic) very dense <u>SP</u>
13.0					3/4" ID Hollow Stem Auger to 13.0'	Light brown of SAND, trace SILT (satur- ated, nonplastic) med. dense - <u>SP</u>
					Sample as above	Light brown of GRAVEL and cmf GRAVEL, trace SILT (saturated, nonplastic) very dense <u>GLW</u>
14.0		S-4A	1 3/8"	100%		
		S-4B	1 3/8"	100%		
15.0					Boring Terminated at 15.0', 11/7/87	

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O.#0018
Page 1 of 4 Pages

Hole No. FD87-10 Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 1/7/87

Co-ordinates: X see X sketch Boring Completed 1/8/87

Drilled by Cambridge & Murdock Report Submitted _____

Purpose of Exploration Determine foundation conditions for proposed
revetments, sluice gate and earth berm

Elevation Top of Hole 1.50 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 25.0 Feet

Elevation Top of Rock _____ M.S.L.

Elevation Bottom of Hole -23.5 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 25.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.; _____ Dim. _____ In.

Soil Samples 13/8 In. Diam. 6 No.

Soil Samples _____ In. Diam. _____ No.

Water Table Depth 5.3'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	23.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling on 5' intervals.
23.0	25.0	1 3/8" ID Split Spoon Sampler

INDEX

Ground Water _____ Back of Page 4
Boring Location Sketch _____ Back of Page 4
Overburden Record _____ Page 2-3
~~Rock Drilling~~ _____ Page _____
_____ Page _____
_____ Page _____

Prepared by T A Beddoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughans Point, Revere MA Page 4 of 4 Pages

Boring No. FD87-10 Desig. J Diam. (Casing) 3 1/4" ID ^{Hollow} _{Auger}

FIELD LOG OF TEST BORING

Coordinates: N see sketch E

Elevation Top of Boring 1.50 M.S.L. Hammer Wt. 140# Boring Started 1/7/87
Total Overburden Drilled 25.0 Feet Hammer Drop 30"
Elevation Top of Rock M.S.L. Casing Left 0' Boring Completed 1/8/87
Total Rock Drilled 0 Feet Subsurface Water Date Page 4
Elevation Bottom of Boring -23.5 M.S.L. Obs. Well no
Total Depth of Boring 25.0 Feet Drilled By Cambridge + Murdock
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CHE 45
Core Recovered 0 Ft : Diam. In. Inspected By: Beddoe
Soil Samples 1 3/8 In. Diam. 6 No. Classification By: Beddoe
Soil Samples In. Diam. No. Classification By:

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" 2'	NO.	SIZE			
0.0'				REL	Sample using 1 3/8" ID by 2' long split spoon sampler	Med. brown cml SAND, little of GRAVEL, trace SHELL FRAGMENTS, trace SILT (wet, nonplastic) medium dense <u>SW</u>
		S-1	1 3/8"	15%		
				3		
				7		
2.0'				13	3/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring.	
				15		
5.0'					Sample as above	Light brown f SAND, trace of GRAVEL, trace SILT (saturated, non- plastic) medium dense
		S-2	1 3/8"	90%		
				8		
				8		
7.0'				9	Auger to 10.0'	<u>SD</u>
				13		
10.0'						

GENERAL REMARKS:

Elevations as surveyed in the field by ATL
using benchmark near FD-S (FD87-20)

All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH		CORE/SAMPLE		BLOWS		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	12.0'	NO.	SIZE	PERCENT	TRAT		
10.0'	12.0'	5-3	1 3/8"	70%	REC	Sample using 1 3/8" ID by 2' long split spoon sampler	Medium brown cf GRAVEL and cmf SAND, trace SILT (saturated, nonplastic) dense, <u>GW</u> with 2" layer of soils similar to S-2
15.0'	17.0'	5-4	1 3/8"	80%	26 31 32 30	Sample as above	Medium grey cmf SAND and cf GRAVEL, trace SILT (saturated, nonplastic) very dense <u>SW</u> with 2" layer of SILT and CLAY, trace f SAND, trace ORGANICS (roots) (saturated, plastic)
20.0'	22.0'	5-5	1 3/8"	25%	34 25 25 16	Auger to 20.0' where encounter difficulty with flowing sands. Attempts to wash out augers with hose were unsuccessful before the returning tide forced us off site. Pull augers. Explorations end 11/7/87	<u>M.H.</u> - Note sulphur odor. (natural). Medium brown f GRAVEL and cmf SAND, trace SILT (sat., nonplastic) dense <u>GP</u>
23.0'	25.0'	5-6	1 3/8"	75%	31 34 26 18	Auger to 23.0' Sample as above.	Light brown cmf SAND, little f. GRAVEL, trace SILT (wet, nonplastic) VERY dense - <u>SW</u>
						Boring Terminated at 25.0' 11/8/87	

Site: Boughan's Point

Boring No: FD87-10


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
 Hole No. FD87-11 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Page 1 of 4 Pages
 Co-ordinates: X see X sketch Boring Started 1/8/87
 Drilled by Todd E Saarinen Boring Completed 1/8/87
 Report Submitted _____

Purpose of Exploration Determine Foundation conditions for proposed
revetments, sluice gate and earth berm.

Elevation Top of Hole 4.00 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 25.00 Feet
 Elevation Top of Rock — M.S.L.
 Elevation Bottom of Hole -21.00 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 25.0 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.; — Diam. — In.
 Soil Samples 13/8 In. Diam. 6 No.
 Soil Samples — In. Diam. — No. Water Table Depth 6.5'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	23.0	3 1/4" ID Hollow Stem Auger with
		1 3/8" ID Split Spoon Sampling at
		5.0' Intervals
23.0	25.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water _____	Back of Page <u>4</u>
Boring Location Sketch _____	Back of Page <u>4</u>
Overburden Record _____	Page <u>2-3</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by TA Beddoe Field Data Lab. Data
 Submitted by Atlantic Testing Labs, Ltd.

DEPTH		CORE/SAMPLE		BLOWS PER FOOT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	1'-2'	NO.	SIZE			
10.0'				REL	19	Med. brown cmf SAND, some cf GRAVEL, trace SILT (wet, nonplastic) very dense <u>SW</u>
		5-3	1 3/8"	100%	29	
					34	
					51	
12.0'						
						Med. brown mf SAND, little cf GRAVEL, trace SILT (saturated, nonplastic) med. dense- <u>SD</u>
15.0'						
					14	Med. brown mf SAND, trace SILT (saturated, nonplastic) med. dense- <u>SD</u>
		5-4	1 3/8"	100%	10	
					7	
					23	
17.0'						
						Med. brown mf SAND, trace SILT (saturated, nonplastic) medium dense <u>SP</u>
20.0						
					20	Med. brown mf SAND, trace SILT (saturated, nonplastic) medium dense <u>SP</u>
		5-5	1 3/8"	80%	24	
					8	
					9	
22.0						
						Med. brown mf SAND, trace SILT (saturated, nonplastic) medium dense <u>SP</u>
23.0						
					7	Med. brown mf SAND, trace SILT (saturated, nonplastic) medium dense <u>SP</u>
		5-6	1 3/8"	80%	7	
					7	
					6	
25.0						
						Boring terminated at 25.0' 1/8/87

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
Page 1 of 4 Pages
Hole No. FD87-12 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} Auger Boring Started 1/8/87
Co-ordinates: X see X sketch Boring Completed 1/8/87
Drilled by Todd E. Saohinen Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berm.

Elevation Top of Hole 1.00 M.S.L.
Total Overburden Drilled 15.0 Feet
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole -14.0 M.S.L.
Total Rock Drilled 0 Feet
Total Depth of Hole 15.0 Feet
Core Recovered 0 %
Core Recovered 0 Ft.: _____ Dim. _____ In.
Soil Samples 13/e In. Dim. 6 No.
Soil Samples _____ In. Dim. _____ No.

Casing Left in Place 0 Feet

Water Table Depth 1.5'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling at 5' intervals
13.0	15.0	1 3/8" ID Split Spoon Sampling

INDEX

Ground Water _____ ~~Back of Page~~ 4
Boring Location Sketch _____ ~~Back of Page~~ 4
Overburden Record _____ Page 2-3
~~Rock Drilling~~ _____ Page _____
_____ Page _____
_____ Page _____

Prepared by TJ Beddoe

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

Site <u>Roughan's Point</u>				Boring No. <u>FD87-12</u>		Page <u>3</u> of <u>4</u>	
DEPTH		CORE/SAMPLE		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS	
1.0'	2'	NO	SIZE	REL	1	Dark grey SILT and CLAY, some mf SAND, trace OR-GANICS (red wood chips, roots), trace F. GRAVEL, trace SHELL FRAGMENTS (saturated, plastic) soft <u>MH "PEAT"</u> change at 11.0' to Light blue-grey CLAY, some SILT, trace mf SAND (wet, plastic) <u>medium CL</u> Dark brown mf SAND, little SILT, trace F GRAVEL, trace CLAY (saturated, very slightly plastic) med. dense <u>SP-SM</u> change @ 14.0' to Medium green-grey with rust mottles SILT, trace fine SAND (moist, nonplastic) dense <u>ML</u>	
		S-3A	1 3/8"	75%	2		
11.0'		S-3B	1 3/8"	75%	2 3		
12.0'							
13.0'							
		S-4A	1 3/8"	50%	8 13	Boring Terminated at 15.0' 1/2/87.	
14.0'		S-4B	1 3/8"	50%	23 24		
15.0'							

Site: Roughan's Point
Boring No: FD87-12


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
Page 1 of 4 Pages

Hole No. ED87-13 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Boring Started 1/8/87

Co-ordinates: X see X sketch Boring Completed 1/8/87

Drilled by Cambridge & Murdock Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berm

Elevation Top of Hole 0.90 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 15.0 Feet

Elevation Top of Rock _____ M.S.L.

Elevation Bottom of Hole -14.1 M.S.L.

Total Rock Drilled 0 Feet

Total Depth of Hole 15.0 Feet

Core Recovered 0 %

Core Recovered 0 Ft.: _____ Diam. _____ In.

Soil Samples 1 3/8 In. Diam. 4 No.

Soil Samples _____ In. Diam. _____ No.

Water Table Depth 5.5'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling at 5.0' intervals
13.0	15.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water _____	Back of Page <u>4</u>
Boring Location Sketch _____	Back of Page <u>4</u>
Overburden Record _____	Page <u>2-3</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by TA Beddoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Boughan's Point, Revere MA Page 3 of 4 Pages

Boring No. FD87-13 Desig. K Diam. (Casing) 3 1/4" ID ^{Hollow} _{Auger}

Co-ordinates: X see sketch X

FIELD LOG OF TEST BORING

Elevation Top of Boring 0.90 M.S.L. Hammer Wt. 140 # Boring Started 1/8/87
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/8/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -14.1 M.S.L. Obs. Well NO
Total Depth of Boring 15.0 Feet Drilled By Cambridge + Murdock
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CHE 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoe
Soil Samples 1 3/8 In. Diam. 4 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" 2'	NO.	SIZE			
0.0'	1" 2'					
				REC		
		S-1	1 3/8"	15%	4 sample using 1 3/8" ID by 2' long split spoon sampler	Med. grey brown cnp sand, some & GRAVEL, trace SHELL FRAGMENTS, trace
2.0'					3/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring	SILT (wet, nonplastic) medium dense <u>SW</u>
5.0'						
		S-2	1 3/8"	50%	6 sample as above	<u>SW</u> as above - saturated
7.0'						
					Auger to 10.0' Note boulders from 7.5' to 9.5'	
10.0'						

GENERAL REMARKS:

Elevations as surveyed in the field by ATL
using benchmark near FD-3. (FD87-20).

All soil sampling performed in accordance with ASTM
D1586 except as noted.

Site

Roughan's Point

Boring No.

FD87-13

Page

3

of

4

DEPTH		CORE/SAMPLE		BLOW COUNT		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	1.0'	NO.	SIZE	FEET	PERCENT		
				REC	31	Sample using 1 3/8" ID by 2' long split spoon sampler.	Medium brown mF SAND, trace of GRAVEL, trace SILT (saturated, nonplastic)
					26		
					28		
					19		
10.0'		S-3	1 3/8"	80%		3 1/4" ID Hollow Stem Auger to 13.0'	dense <u>SP</u>
13.0'							
					26	Sample as above	Dark grey mF SAND, little GRAVEL, trace SILT (saturated, nonplastic)
					24		
					25		
					20		
15.0'		S-4	1 3/8"	30%		Boring Terminated at 15.0' 1/8/87	dense <u>SL</u>

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O. #0018
Site Roughan's Point, Revere MA Page 1 of 5 Pages
Hole No. FD87-14 Diam. (Casing) 3 1/4" ID Augers Hollow Stem
Co-ordinates: X see sketch Boring Started 1/14/87
Drilled by Cambridge & Mundock Boring Completed 7/14/87
Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth beam

Elevation Top of Hole 5.40 M.S.L. Casing Left in Place 0 Feet
Total Overburden Drilled 37.0 Feet
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole -31.6 M.S.L.
Total Rock Drilled 0 Feet
Total Depth of Hole 37.0 Feet
Core Recovered 0 %
Core Recovered 0 Ft.; _____ Diam. _____ In.
Soil Samples 13/8 In. Diam. 11 No.
Soil Samples _____ In. Diam. _____ No. Water Table Depth 8.0'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	35.0	3 1/4" Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling at 5' intervals
25.0	37.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water _____	Back of Page <u>5</u>
Boring Location Sketch _____	Back of Page <u>5</u>
Overburden Record _____	Page <u>2-4</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by TJ Beddoe Field Data _____ Lab. Data _____
Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughans Point, Revere, MA Page 5 of 5 Pages

Boring No. FD87-14 Desig. W Diam. (Casing) 3 1/4" ID ^{Hollow} _{Auger}

FIELD LOG OF TEST BORING

Co-ordinates: N = sketch E

Elevation Top of Boring 5.40 M.S.L. Hammer Wt. 140# Boring Started 1/14/87
Total Overburden Drilled 37.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/14/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 5
Elevation Bottom of Boring - 31.6 M.S.L. Obs. Well no
Total Depth of Boring 37.0 Feet Drilled By Cambridge + Murdock
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddor
Soil Samples 1 3/8 In. Diam. 11 No. Classification By: Beddor
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" = 2'	NO.	SIZE	DEPTH RANGE REMARKS		
2.0'		S-1	1 3/8"	50% REC	3 2 3 5 Sample using 1 3/8" ID by 2' long split spoon sampler.	Medium brown SILT, little F. SAND, trace ORGANICS (wood chips, roots) (moist, nonplastic) ^{medium} <u>ML</u>
5.0'					3 1/4" ID Hollow Stem Auger to 5.0' Augering easy throughout boring.	(Material had been previously disturbed by bulldozer)
7.0'		S-2	1 3/8"	50%	4 4 4 8 Sample as above	Medium grey-brown <u>ML</u> as above, with trace of GRAVEL
10.0'					Auger to 10.0'	(Material <u>not</u> previous- ly disturbed by bull- dozer)

GENERAL REMARKS:

Elevations as surveyed in the field by ATL
using benchmark near FD-5, (FD87-20)
Boring 12.0' deeper than requested to compensate
for change in boring location which elevated
the boring 12.0'. Please see Note, Page 4.

Note! All soil sampling per-
formed in accordance
with ASTM D1586 except
as noted.

Boring No. FD87-14

Site				Boring No.		Page	
Roughans Point				FD87-14		3	
DEPTH		CORE/SAMPLE		BLOW		6" SAMPLING AND CORING	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.		OPERATIONS	
10.0'		1.0'		NO.			

DEPTH		CORE/SAMPLE		BLOWS PER FOOT		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
NO.	SIZE	NO.	SIZE	NO.	SIZE		
27.0'	1" 2'					3 1/4" ID Hollow Stem Auger to 30.0'	
30.0'							
32.0'		S-7	1 3/8"	90%	15 10 7 6	Sample using 1 3/8" ID by 2' long split spoon sampler.	Medium grey fine SAND, trace of GRAVEL, trace SILT (saturated, nonplastic)
35.0'						Auger to 35.0'	medium dense <u>SW</u>
37.0'		S-8	1 3/8"	100%	16 10 7 16	Sample as above.	<u>SW</u> as above
						Boring Terminated at 37.0' 11/14/87	
						Note: Boring location had been regraded by bulldozer which removed bushes and trees and cleared a road to the boring. Final grade was approximately one foot higher than initial grade at the boring location. No soil was removed, only bushes and trees with whatever topsoil would have been disturbed in that process.	

Site: Daughan's Point

Boring No: FD87-14


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere, MA PROJECT NO. D.O. #0018
Page 1 of 8 Pages
Hole No. FD87-15 Diam. (Casing) 4"r Boring Started 1/12/87
Co-ordinates: X see X sketch Boring Completed 2/8/87
Drilled by Cambridge & Burnham Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms

Elevation Top of Hole 7.70 M.S.L. Casing Left in Place 0 Feet
Total Overburden Drilled 54.0 Feet
Elevation Top of Rock — M.S.L.
Elevation Bottom of Hole -46.3 M.S.L.
Total Rock Drilled 0 Feet
Total Depth of Hole 54.0 Feet
Core Recovered 0 %
Core Recovered 0 Ft.; — Diam. — In.
Soil Samples 1 3/8 In. Diam. 14 No.
Soil Samples 3 In. Diam. 1 No. Water Table Depth 8.0'

Depth		Method of Drilling * and Type of Bit Used	INDEX
From	To		
0.0	5.0	track backhoe	Ground Water <u>Back of Page 8</u>
5.0	10.0	3/4" ID Hollow Stem Auger	Boring Location Sketch <u>Back of Page 8</u>
10.0	30.0	4" spun-in casing cleaned out by 3 7/8" OD roller bit	Overburden Record <u>Page 2-5</u>
30.0	52.0	3 7/8" OD roller bit in open hole	Rock Drilling <u>Page</u>
52.0	54.0	1 3/8" ID split spoon sampler	Field Log of Undisturbed Sampling <u>Page 6+</u>
		*includes samples taken every 5'	<u>Page</u>
		or less using either 1 3/8" ID split spoon sampler or 3" ID undisturbed sampler	<u>Page</u>

Prepared by TJ Beddoe

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Dougham's Point, Revere MA Page 2 of 8 Pages

Boring No. ED87-15 Desig. 0 Diam. (Casing) 4"

FIELD LOG OF TEST BORING

Co-ordinates: X see sketch R

Elevation Top of Boring 7.70 M.S.L. Hammer Wt. 140# Boring Started 1/12/87
Total Overburden Drilled 54.0 Feet Hammer Drop 30"
Elevation Top of Rock M.S.L. Casing Left 0' Boring Completed 2/8/87
Total Rock Drilled 0 Feet | Subsurface Water Data | Page 8
Elevation Bottom of Boring -46.3 M.S.L. | Obs. Well NO
Total Depth of Boring 54.0 Feet | Drilled By Cambridge & Burnham
Core Recovered 0 % No. Boxes 0 | Mfg. Des. Drill CHE 45
Core Recovered 0 Ft : Diam. In. | Inspected By: Reddick
Soil Samples 1 3/8 In. Diam. 14 No. | Classification By: Reddick
Soil Samples 3 In. Diam. 1 No. | Classification By:

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0	1" 2'	NO.	SIZE	DEPTH RANGE		
					Five feet of boulders removed by subcontracted track backhoe	Boulders (rip rap) 1 ft ³ to 10 ft ³ in size; interstitial material - air.
5.0					Explorations end 1/12/87	
				3	Explorations begin 1/20/87	Medium brown cme SAND,
				10	Sample using 1 3/8" ID by	some of GRAVEL, trace
		5-1	1 3/8"	15 2	2' long split spoon	SHELL FRAGMENTS,
				4	sampler	
7.0				20	3/4" ID Hollow Stem auger to 10.0'	trace SILT (wet, non-plastic) medium dense
					Augering easy.	<u>SUO</u>
10.0'						

GENERAL REMARKS:

Elevations as determined in the field by ATL using benchmark near FD-5 (FD87-20)

All soil sampling performed in accordance with ASTM D1586 except as noted. (UD-1 and UD-2, ASTM D1587).

Boring No. ED87-15

DEPTH		CORE/SAMPLE			BLOWS PER FEET	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0	1.2'	NO	SIZE	PERCENT RECOVERY			
				REC	4	Sample using 1 3/8" ID by 2' long split spoon sampler.	Medium grey with brown
		S-2	1 3/8"	25%	4	Remove 3 1/4" ID hollow stem augers	flecks SILT, little OR-
12.0					2	Explorations end 1/20/87	GANICS (unidentifiable)
						Explorations begin 1/29/87	trace CLAY (wet, very
						spin 4 1/2" ID casing to 15'	slightly plastic) ^{medium} stiff
						Material easy to penetrate to 30.0'	
15.0						Wash out using 3 7/8" OD roller bit.	<u>ML</u> Note sulphur odor (natural)
					5	Sample as above	Med. grey CLAY, some SILT,
		S-3	1 3/8"	45%	2		little med SAND, trace F
					4		
17.0					4	Explorations end 1/29/87	GRAVEL (saturated, plas-
						Explorations begin 2/3/87	tic) ^{medium} stiff <u>CL</u> (Note odor of petroleum contaminant from refuse)
						Spin casing to 19.5'	Med. grey SILT and CLAY,
						Wash out	trace med SAND (sat, plastic) stiff <u>MF</u>
19.2							
19.7		S-4A	1 3/8"	80%	8	Attempt an undisturbed sample (see page 6)	Med. grey/brown SILT, little
		S-4B	1 3/8"	80%	7	Sample by split spoon	CLAY (moist, slightly
20.7					11	as above at same elevation.	plastic) ^{very} stiff <u>ML</u>
21.2		S-4C	1 3/8"	80%	11		Soils similar to S-4B with trace F. SAND.
						Spin casing to 24.0'	<u>ML</u>
						Note change in material consistently at 21.5'	
						Explorations end 2/3/87 AM	
						Explorations begin 2/3/87 PM	
25.0						Advance 3 7/8" roller bit to 25'	Light brown SILT and CLAY
		S-5	1 3/8"	5%	10	Sample using split spoon as above. First sample yielded no recovery. Second attempt with new basket yielded 5% recovery.	little med SAND (sat, plastic) stiff <u>ML</u>
					7		
					9		
27.0					8		

Site Roughan's Point				Boring No FD87-15		Page 4 of 8	
DEPTH	CORE/SAMPLE		BLOW COUNT		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
27.0'	1" O.D.	NO	SIZE	PERCENT REMARKS			
27.0'				REL	Spin 4" casing to 30'. Clean out using 3 7/8" O.D. roller bit	See material description page 3	
30.0'		S-6	1 3/8"	15%	25 47 42 27 sample using 1 3/8" ID key 2' long split spoon sample.	light grey-brown SILT, little CLAY, trace f SAND (saturated, slightly plastic) hard <u>ML</u>	
32.0'					Explorations end 2/3/87 PM Explorations begin 2/4/87 AM Advance 3 7/8" roller bit to 35'. Material diffi- cult to penetrate to 40.0'	with 1/8" layer SILT - Note odor of petro- leum contamination from off-site and soft blebs of clayey silt.	
35.0'					Sample as above	light grey CLAY, some SILT, little cmf SAND, trace	
37.0'		S-7	1 3/8"	25%	50 62 59 50	f GRAVEL (sat., plastic) hard <u>CL</u> Note odor of petroleum product (offsite contaminant)	
40.0'					Advance roller bit to 40'.	Light grey CLAY, some SILT, trace f. SAND, (sat., plastic) still <u>CL</u>	
41.5'		S-8A	1 3/8"	100%	6 7 7 Sample as above	Note no odor.	
42.0'		S-8B	1 3/8"	100%	8 Explorations end 2/4/87 AM Explorations begin 2/4/87 PM Advance roller bit to 45'. Material easy to penetrate to 46.5'	Soils similar to S-6 with 2" layer of soils similar to S-8A. Note petroleum odor. (offsite contaminant) <u>ML</u>	
44.0'							

Site				Boring No.				Page					
Roughan's Point				FD87-15				5					
								of					
								8					
DEPTH		CORE/SAMPLE		BLOW COUNT		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS					
44.0'		2'		NO		SIZE		REMARKS					
44.8'				REC									
46.5'		UD-2 3"		100%		N/A		Take undisturbed sample (see page 7). Sample description from disturbed material at top of tube.		Med grey-brown CLAY, some SILT, little c.m.f. SAND (sat., plastic) <u>CL</u>			
48.5'		S-9 1 3/8"		25%		35 32 21 14		Sample using 1 3/8" ID by 2' long split spoon sampler to determine character of soils which caused UD-2 tube refusal.		Med. grey m.f. SAND, some SILT, little CLAY, trace of GRAVEL (sat., slightly plastic) dense SM-SC			
49.0'								Explorations end 2/4/87 PM		Note petroleum odor - ^{off-site} contaminant			
51.0'		S-10 1 3/8"		25%		17 17 17		Explorations begin 2/5/87		Med grey m.f. SAND and c.f. GRAVEL, trace SILT (sat., nonplastic) dense			
52.0'								Material difficult to penetrate to end of boring. Sample using split spoon.		SP Note odor of petroleum product ^{off-site} (contaminant)			
54.0'		S-11 1 3/8"		40%		65 45 45 35		Advance roller bit to 52'. Note caving at 50'. Explorations end 2/5/87		Med brown-grey soils similar to S-10. SP - TILL			
								Explorations begin 2/8/87		Note faint petroleum odor ^{off-site} (contaminant).			
								Clean hole using roller bit, to 52'. Note caving to 51' which required extensive cleaning.					
								Sample using split spoon.					
								Boring terminated, as directed by the Corps, at 54.0'; 2/8/87.					

FIELD LOG OF UNDISTURBED SAMPLING IN DRILL HOLES

SITE Pougham's Point, Revere MA HOLE NO. FD87-15 DATE 2/3/87SAMPLE NO. 45-1 INSPECTOR Beddoe DRILLER Cambridge

A	Total Length of Casing	15.3	
B	Casing Length above Ground	0.8	
C	Depth of Bottom of Casing (Below Ground) (A-B)	14.5	
D	Length of Sampler and Drill Rods	22.9	
E	Drill Rods Length above Ground	8.7	
F	Depth of Bottom of Clean-Out Auger (below ground) (D-F)	14.2	
G	Distance of Bottom of Auger above or below Casing (F-C)	- 0.3	
		Drill Rods, (1)	Piston Rods, (2)
H	Total Length, Sampler and Rods	22.9	X
I	Length of Rods above Ground	8.7	
J	Depth of Bottom of Sampler (below ground) (H-I) (1) & (2), (Depth of Top of Sample)	14.2	
K	Penetration of Sampler, (K-F) (1)	1.3	
L	Penetration or Swell of Piston (K-F)(2)	N/A	
Data after Jacking			
M	Length of Sampler and Piston Rods above Ground	7.4	N/A
N	Length of Drive (I-M)(1)	1.3	
O	Piston Displacement (I-M) (2)	N/A	
P	Length of Sample Recovered	0.0	
Q	Length of Sample Lost	1.3	
R	Amount of Sample Recovered, $\%, \frac{P}{N} \times 100$	0%	
S	Type and Size of Sampler 3"OD tube, total length 2.9'		
T	Method and Time of Penetration steady down pressure using Mq 9:30 AM		
U	Type of Materials Sampled clayey silt - see S-4, page 3		
<p>Other Notes and Remarks: note that top of boring is 5.0' above ground surface. length of sampler 2.9' sampler was refused after 1.3' penetration. sampler allowed to sit 10 minutes, given one full twist. no recovery - bottom of sampler warped badly by refusal split spoon sample taken at same elevation (see S-4)</p>			

FIELD LOG OF UNDISTURBED SAMPLING IN DRILL HOLES

SITE Roughan's Point, Revere MA HOLE NO. FD87-15 DATE 2/4/87SAMPLE NO. UD-2 INSPECTOR Beddoe DRILLER Cambidge

A	Total Length of Casing	20.3	
B	Casing Length above Ground	1.3	
C	Depth of Bottom of Casing (Below Ground) (A-B)	19.0	
D	Length of Sampler and Drill Rods	42.9	
E	Drill Rods Length above Ground	3.1	
F	Depth of Bottom of Clean-Out Auger (below ground) (D-F)	39.8	
G	Distance of Bottom of Auger above or below Casing (F-C)	20.8	
		Drill Rods, (1)	Piston Rods, (2)
H	Total Length, Sampler and Rods	42.9	X
I	Length of Rods above Ground	3.1	
J	Depth of Bottom of Sampler (below ground) (H-I) (1) & (2), (Depth of Top of Sample)	39.8	
K	Penetration of Sampler, (K-F) (1)	1.7	
L	Penetration or Swell of Piston (K-F) (2)	N/A	
Data after Jacking			
M	Length of Sampler and Piston Rods above Ground	1.4	N/A
N	Length of Drive (I-M) (1)	1.7	
O	Piston Displacement (I-M) (2)	N/A	
P	Length of Sample Recovered	1.7	
Q	Length of Sample Lost	0.0	
R	Amount of Sample Recovered, $\% \frac{P}{N} \times 100$	100%	
S	Type and Size of Sampler 3" OD tube, tube length 2.5', total 2.9'		
T	Method and Time of Penetration steady down pressure using Hg/9:20 PM		
U	Type of Materials Sampled silty clay - see description, page 5		

Other Notes and Remarks:

Note that top of boring is 5.0' above ground surface. Sampler was refused after 1.7' penetration. Sampler allowed to sit 10 minutes, given one full twist.

Recovered sample came to base of sampler. Base was capped, taped and sealed in beeswax. Top of sample capped in tube with beeswax. Remainder of tube filled with beach sand. Tube was capped, taped and sealed with beeswax.

Site: Roughan's Point


Boring No: FD87-15

SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH



Not to Scale

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
Page 1 of 4 Pages
Hole No. FD87-16 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Boring Started 1/21/87
Co-ordinates: X see X sketch Boring Completed 1/21/87
Drilled by Cambridge & Burnham Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berm

Elevation Top of Hole -3.30 M.S.L. Casing Left in Place 0 Feet
Total Overburden Drilled 15.0 Feet
Elevation Top of Rock — M.S.L.
Elevation Bottom of Hole -18.3 M.S.L.
Total Rock Drilled 0 Feet
Total Depth of Hole 15.0 Feet
Core Recovered 0 %
Core Recovered 0 Ft.; — Diam. — In.
Soil Samples 1 3/8 In. Diam. 5 No.
Soil Samples — In. Diam. — No. Water Table Depth surface

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	13.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling at 5' intervals
13.0	15.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water	Back of Page <u>4</u>
Boring Location Sketch	Back of Page <u>4</u>
Overburden Record	Page <u>2-3</u>
Rock Drilling	Page _____
	Page _____
	Page _____
	Page _____

Prepared by JABedder

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughams Point, Revere MA Page 3 of 4 Pages
Boring No. FD87-16 Desig. N Diam. (Casing) 3/4" Hollow Stem Auger
Co-ordinates: X see sketch X

FIELD LOG OF TEST BORING

Elevation Top of Boring -9.30 M.S.L. Hammer Wt. 140# Boring Started 1/21/87
Total Overburden Drilled 15.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/21/87
Total Rock Drilled 0 Feet Subsurface Water Date — Page 4
Elevation Bottom of Boring -18.3 M.S.L. Obs. Well no
Total Depth of Boring 15.0 Feet Drilled By Cambridge + Burnham
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoe
Soil Samples 13/8 In. Diam. 5 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" 2'	NO.	SIZE	DEPTH RANGE		
				REC	30	
		S-1	1 3/8"	10%	20	
					17	
2.0'					5	
5.0'						
7.0'		S-2	1 3/8"	20%	5	
					3	
					2	
					6	
10.0'						
GENERAL REMARKS: Elevations as surveyed in the field by ATL using benchmark near FD-S. (FD87-20) All soil sampling performed in accordance with ASTM D1586 except as noted.						Hed. brown & GRAVEL, some SILT, some ORGANICS (wood chips), trace m&f SAND (saturated, non- plastic) med. dense GP-GM (Note numerous surficial cobbles and coarse gravel - recovered sample not considered typical of surficial soils.) Med. grey & GRAVEL and m&f SAND, trace SILT (saturated, nonplastic) loose <u>SW</u> with 3" layer of Dark red-brown SILT, trace & SAND (wet, nonplastic) med. <u>still</u> PEAT- <u>OL</u> (Note natural sulphur odor.)

Site

Doughans Point

Boring No.

FD87-16

Page 3

of 4

DEPTH		CORE/SAMPLE		BLOWS PER FOOT CORE RECEIVED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
		NO.	SIZE			
12.0'	2'					
		S-3	1 3/8"	5%	10 10 14 13 Sample using 1 3/8" ID by 2' long split spoon sampler	Dark red-brown SILT, trace of GRAVEL, trace of SAND (sat., v. slightly plastic)
12.0'					3 1/4" Hollow stem Auger to 13.0'	very stiff - PEAT - OL (Note natural sulphur odor.)
13.0'					Sample as above	OL as above
14.0'		S-4A	1 3/8"	100%	5 6	Light green-grey / rust SILT, some CLAY, trace
15.0'		S-4B	1 3/8"	100%	6 6	of SAND (saturated, mod. plastic) stiff. MH
					Boring Terminated at 15.0' 1/21/87	

Site: Roughan's Point

Boring No: FD87-16

SUBSURFACE WATER OBSERVATIONS


[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH

Atlantic Ocean



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
 Hole No. FD87-17 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Page 1 of 4 Pages
 Co-ordinates: X see X sketch Boring Started 1/22/87
 Drilled by Cambridge & Burnham Boring Completed 1/22/87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed revetments,
sluice gate and earth berms

Elevation Top of Hole 2.00 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 20.00 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole -18.00 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 20.00 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.; _____ Diam. _____ In.
 Soil Samples 13/8 In. Diam. 10 No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth dry

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
2.0	18.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID	Ground Water _____ Back of Page <u>4</u>
		Split Spoon Sampling at 5' intervals	Boring Location Sketch _____ Back of Page <u>4</u>
18.0	20.0	1 3/8" Split Spoon Sampler	Overburden Record _____ Page <u>2-3</u>
			Rock Drilling _____ Page _____
			_____ Page _____
			_____ Page _____
			_____ Page _____

Prepared by YB eddoo Field Data _____ Lab. Data _____
 Submitted by Atlantic Testing Laboratories, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughan's Point, Revere MA Page 3 of 4 Pages

Boring No. FD37-17 Desig. R Diam. (Casing) 3/4" ID ^{Hollow} _{Auger}

Co-ordinates: N see sketch X

FIELD LOG OF TEST BORING

Elevation Top of Boring 2.00 M.S.L. Hammer Wt. 140# Boring Started 1/22/87
Total Overburden Drilled 20.0 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/22/87
Total Rock Drilled 0 Feet Subsurface Water Data — Page 4
Elevation Bottom of Boring -18.0 M.S.L. Obs. Well no
Total Depth of Boring 20.0 Feet Drilled By Cambodge & Burnham
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CHE45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Reddick
Soil Samples 1 3/8 In. Diam. 10 No. Classification By: Reddick
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0'	1" 2'	NO.	SIZE	DEPTH RANGE RECOVERY		
				REC	3	Medium gray-brown cml SAND, little of GRAVEL, trace SILT (wet, nonplastic) mod. medium dense <u>SW</u>
		S-1	1 3/8"	40%	11	
					17	
20'					14	
						8 1/4" ID Hollow Stem Auger to 5.0' Note a few boulders from 3.0-5.0'
5.0'						
		S-2A	1 3/8"	100%	3	<u>SW</u> as above - saturated, loose
6.0'					3	
		S-2B	1 3/8"	100%	3	Dark brown SILT and ORGANIC (rocks, wood chips), trace of SAND, (wet, nonplastic) medium stiff
7.0'					3	
						<u>OL</u> PEAT Note natural sulphur odor.

GENERAL REMARKS:

Elevations as surveyed in the field by ATL using bench-
mark near FB-5. (FD87-20)

All soil sampling performed in accordance with ASTM
D1586 except as noted.

5112					Boring No.		FD87-17		Page <u>3</u>	
Roughan's Point									of <u>4</u>	
DEPTH		CORE/SAMPLE		BLOWS		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS		
10.0	1.2'	NO	SIZE	REMARKS	REMARKS					
				REC	2	Sample using 1 3/8" ID by 2' long split spoon sampler		Soils Similar to S-2B		
		S-3	1 3/8"	50%	2			<u>OL</u> PEAT		
					2					
12.0					4					
						3 1/4" ID Hollow Stem Auger to 15.0'				
								Soils Similar to S-2B		
								saturated - <u>OL</u> PEAT		
15.0								Light grey/just SILT,		
15.7		S-4A			4	Sample as above		little CLAY, trace F		
					6			SAND, trace F GRAVEL		
16.3		S-4B	1 3/8"	85%	7			(wet, slightly plastic) stiff		
								<u>ML</u>		
17.0		S-4C			11			Medium grey m SAND and		
						Auger to 18.0'		SILT, trace F GRAVEL,		
18.0								trace CLAY (sat, very		
		S-5A			15	Sample as above		slightly plastic) ^{medium} dense - <u>SL</u>		
			1 3/8"	100%	19			Dark brown SILT, some ORGANICS		
19.3					17			(roots, wood chips) trace		
19.7		S-5B			23			F. SAND, trace F.		
20.0		S-5C						GRAVEL, trace CLAY		
						Boring Terminated at 20.0' 1/22/87		(sat, v. sl. plastic) <u>ML</u>		
								(Note natural sulphur odor)		
								Medium blue-grey CLAY		
								and SILT, trace F. SAND		
								(saturated, plastic)		
								hard <u>CL</u>		
								Light yellow/green mottled		
								SILT and m SAND, little		
								F GRAVEL, trace CLAY		
								(wet, very slightly plastic)		
								hard <u>ML</u>		

Site: Roughan's Point

Boring No: FD87-17

SUBSURFACE WATER OBSERVATIONS

[illegible]


Note: Depths are in feet below original ground

Not to Scale.

BORING LOCATION SKETCH

Note: As-built boring location is the requested location.

Atlantic Ocean



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
 Hole No. FD97-18 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Page 1 of 4 Pages
 Co-ordinates: X see X sketch Boring Started 1/28/87
 Drilled by Cambridge & Burnham Boring Completed 1/28/87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms

Elevation Top of Hole -2.20 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 20.0 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole -22.20 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 20.0 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.; _____ Diam. _____ In.
 Soil Samples 1 3/8 In. Diam. 10 No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth 13.0'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	18.0	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling at 5' intervals
18.0	20.0	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water _____	Back of Page <u>4</u>
Boring Location Sketch _____	Back of Page <u>4</u>
Overburden Record _____	Page <u>2-3</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by TA Beddoe Field Data _____ Lab. Data _____
 Submitted by Atlantic Testing Labs, Ltd.


Boring No. FD87-18

[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O.#0018
Site Roughan's Point, Revere MA Page 1 of 4 Pages
Hole No. ED87-19 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} ~~Auger~~ Boring Started 1/28/87
Co-ordinates: X see X sketch Boring Completed 1/28/87
Drilled by Cambridge + Burnham Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms

Elevation Top of Hole -3.80 M.S.L. Casing Left in Place 0 Feet
Total Overburden Drilled 11.75 Feet
Elevation Top of Rock — M.S.L.
Elevation Bottom of Hole -15.55 M.S.L.
Total Rock Drilled 0 Feet
Total Depth of Hole 11.75 Feet
Core Recovered 0 %
Core Recovered 0 Ft.; — Diam. — In.
Soil Samples 13/8 In. Diam. 3 No.
Soil Samples — In. Diam. — No. Water Table Depth 1.5'

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0.0	10.0	3 1/4" ID Hollow Stem Auger with 1 3/8"	Ground Water	<u>Back of Page 4</u>
		1D Split Spoon Sampling every 5'	Boring Location Sketch	<u>Back of Page 4</u>
10.0	11.75	1 3/8" ID Split spoon sampler	Overburden Record	<u>Page 2-3</u>
			Rock Drilling	<u>Page</u>
				<u>Page</u>
				<u>Page</u>
				<u>Page</u>

Prepared by TA Reddick Field Data
Submitted by Atlantic Testing Labs. Ltd. Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughan's Point, Revere MA Page 8 of 4 Pages

Boring No. FD87-19 Desig. I Diam. (Casing) 3/4 "Hollow Stem Auger

FIELD LOG OF TEST BORING

Co-ordinates: X see sketch E

Elevation Top of Boring -3.80 M.S.L. Hammer Wt. 140^{lb} Boring Started 1/28/87
Total Overburden Drilled 17.75 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 1/28/87
Total Rock Drilled 0 Feet (Subsurface Water Data) — Page 4
Elevation Bottom of Boring -15.55 M.S.L. Obs. Well No
Total Depth of Boring 11.75 Feet Drilled By Cambridge + Burnham
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoe
Soil Samples 13/8 In. Diam. 3 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" 2'	NO.	SIZE			
0.0'				REL	7	Light brown & GRAVEL and fine SAND, trace SILT (saturated, non- plastic) ^{very} dense <u>GW-6M</u> TILL
		S-1	1 3/8"	85%	25 2' long split spoon sampler 60	
2.0'					95	
					3/4" ID Hollow Stem Auger to 5.0'	
5.0'					Note materials hard to penetrate. cobbles and boulders encoun- tered throughout boring.	Light brown fine SAND, little & GRAVEL, trace SILT (moist, nonplas- tic) ^{very} dense <u>SD</u> TILL Note petroleum odor (offsite contaminant).
		S-2	1 3/8"	60%	27 Sample as above 36	
7.0'					41	
					37	
10.0'					Auger to 10.0'	

GENERAL REMARKS:

Elevation as surveyed in the field by ATL using
benchmark near FD-S. (FD87-20)
Boring located in a boulder field/mussel
colony.
All soil sampling performed in accordance with

Site Roughan's Point	Boring No. FD87-19	Page 3 of 4
--------------------------------	------------------------------	------------------------------

DEPTH		COHE/SAMPLE		BLOW COUNT REMARKS	64 SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	1" 21	NO	SIZE			
				REC	sample using 1 3/8" ID by 2' long split spoon sampler.	SP as above - TILL
11.75'		S-3	1 3/8"	80% 63 50/3"	Note bouncing refusal. Boring terminated at 11.75' 1/28/87	

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Rougham's Point, Revere MA PROJECT NO. D.O. #0018
 Hole No. ED87-20 Diam. (Casing) 3 1/4" ID ^{Hollow Stem} Auger Page 1 of 5 Pages
 Co-ordinates: X see X sketch Boring Started 2-6-87
 Drilled by Cambridge + Burnham Boring Completed 2-6-87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms

Elevation Top of Hole 10.10 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 29.8 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole -19.70 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 29.8 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.: _____ Diam. _____ In.
 Soil Samples 13/8 In. Diam. 9 No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth 11.8'

Depth		Method of Drilling and Type of Bit Used
From	To	
0.0	3.5	Track backhoe
3.5	28.5	3 1/4" ID Hollow Stem Auger with 1 3/8" ID Split Spoon Sampling at 5' Intervals
28.5	29.8	1 3/8" ID Split Spoon Sampler

INDEX	
Ground Water _____	Back of Page <u>5</u>
Boring Location Sketch _____	Back of Page <u>5</u>
Overburden Record _____	Page <u>2-4</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by Beddow Field Data _____ Lab. Data _____
 Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughan's Point, Revere MA Page 4 of 5 Pages

Boring No. FD87-20 Desig. S Diam. (Casing) 3 1/4" ID Stem

Auger

FIELD LOG OF TEST BORING

Co-ordinates: X see sketch R

Elevation Top of Boring 10.10 M.S.L. Hammer Wt. 140# Boring Started 2-6-87
Total Overburden Drilled 29.80 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left 0' Boring Completed 2-6-87
Total Rock Drilled 0 Feet | Subsurface Water Date — | Page 5
Elevation Bottom of Boring -19.70 M.S.L. | Obs. Well NO
Total Depth of Boring 29.8 Feet Drilled By Cambridge & Burnham
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CME 45
Core Recovered 0 Ft : — Diam. — In. Inspected By: Beddoe
Soil Samples 1 3/8 In. Diam. 9 No. Classification By: Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" 2'	NO.	SIZE	DEPTH RANGE		
					Three and one half feet of boulder rip rap removed by subcontracted track backhoe	Boulders (rip rap) 1 ft 3 to 10 ft 3 in size; interstitial material - air
3.5'						
		S-1	1 3/8"	20%	Sample using 1 3/8" ID by 2' long split spoon sampler.	Medium brown cmf SAND, trace P. GRAVEL, trace SHELL FRAGMENTS, trace
5.5'					3 1/4" ID hollow stem Auger to 8.5' Note boulder from 4.0 - 4.5 removed using a shovel. Augering occurs to 24.5'	SILT (wet, nonplastic) loose <u>SW</u>
8.5'						
		S-2	1 3/8"	5%	Sample as above. First sample yielded no recovery. Second yielded 5% recovery.	Medium brown cmf SAND, and P. GRAVEL, trace
10.0'						SILT (wet, nonplastic) medium dense <u>SW</u> Note hydrocarbon contam- inant odor. (from offsite)

GENERAL REMARKS:

Elevations as surveyed in the field by ATL using the
benchmark near FD-5 (FD87-20)

All soil sampling performed in accordance with ASTM
D1586 except as noted.

DEPTH	CORE/SAMPLE	BLOW COUNT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	NO	SIZE	PERCENT	
10.0'	2			
10.5'	S-2	1 3/8"	5%	12
13.5'				
	S-3	1 3/8"	100%	3 4 4 4
15.5'				
18.5'				
20.5'	S-4	1 3/8"	50%	7 10 33 21
23.5'				
24.5'	S-5A	1 3/8"	75%	6 16
25.0'	S-5B	1 3/8"	75%	30
25.5'	S-5C	1 3/8"	75%	23
27.0'				

Sample using 1 3/8" ID. by 2' long split spoon sampler.
 3/4" ID Hollow Stem Auger to 13.5'
 Note coarse gravel, cobbles 10.0'-11.0'

Sample as above

Auger to 18.5'
 Note change in material consistency at 16.0'
 wash out augers with hose, cleanout with split spoon sampler.

Sample as above.

Auger to 23.5'

Sample as above

Auger to 28.5'
 Note change in material consistency at 26.5'
 Augering difficult.

Material as described Page 2.

DARK brown ORGANIC MATERIAL (roots) and SILT, trace & SAND (wet, nonplastic) medium stiff OL
 Note sulphur odor (natural)

Med. grey mf SAND, some of GRAVEL, little CLAY, trace SILT (saturated, slightly plastic) dense
SP-SC Note odor of petroleum product (off site pollutant).
 Dark brown SILT and mf SAND, some ORGANICS (roots), trace CLAY, trace & GRAVEL (sat, very slightly plastic) hard M medium brown & SAND and of GRAVEL, little CLAY, trace SILT (sat., sl. plastic) very dense SPSC


DEPTH	CORL/SAMPLE	BLOW COUNT	CORL REMARKS	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIAL:
27.0	2'				
28.5'				3/4" ID Hollow Stem Auger to 28.5. clean auger out with split spoon sampler.	Med. moist-brown & SAND, trace SILT (saturated, non- plastic) dense <u>SP</u>
29.1'	S-6A	1 3/8"	100%	54 115 Sample using 1 3/8" ID by 2' long split spoon sampler.	Light brown soils as above <u>SP</u>
29.8'	S-6B	1 3/8"		115 1/4" Note Bouncing Refusal	Medium brown & GRAVEL and mt SAND, trace SILT
				Boring Terminated @ 29.8' 2/6/87	(moist, nonplastic) very dense <u>GW</u> TILL

[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
 Hole No. FD97-24 Diam. (Casing) 4" Page 1 of 8 Pages
 Co-ordinates: X see & sketch Boring Started 2/11/87
 Drilled by Cambidge & Burnham Boring Completed 2/19/87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
rectments, sluice gate and earth berms

Elevation Top of Hole 5.40 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 56.5 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole -51.1 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 56.5 Feet
 Core Recovered 0 %
 Core Recovered 0 Ft.: _____ Diam. _____ In.
 Soil Samples 1 3/8 In. Diam. 9 No.
 Soil Samples 2 In. Diam. 1 No. Water Table Depth 2.7'

Depth		Method of Drilling * and Type of Bit Used
From	To	
0	50	ROLLER WASH BIT
50	56.5	DIAMOND BIT CORE BARREL
		*includes samples taken every 5' or less using 1 3/8" ID split spoon sampler or 3" ID undisturbed sampler

1390X

Ground Water _____ Back of Page 8
 Boring Location Sketch _____ Back of Page 8
 Overburden Record _____ Page 2-5
 Rock Drilling _____ Page _____
 Field Log of Undisturbed Sampling Page 6-7
 _____ Page _____
 _____ Page _____

Prepared by T. Beddor, PM Fisher
 Field Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Roughan's Point, Revere MA Page 2 of 8 Pages

Boring No. FD87-21 Desig. Q Diam. (Casing) 4"

FIELD LOG OF TEST BORING

Co-ordinates: N see sketch E

Elevation Top of Boring 5.40 M.S.L. Hammer Wt. 140# Boring Started 2/11/87
Total Overburden Drilled 56.5 Feet Hammer Drop 30"
Elevation Top of Rock - M.S.L. Casing Left 0' Boring Completed 3/19/87
Total Rock Drilled 0 Feet (Subsurface Water Data - Page 8)
Elevation Bottom of Boring -51.1 M.S.L. Obs. Well no
Total Depth of Boring 56.5 Feet Drilled By Cambridge and Burnham
Core Recovered 0 % No. Boxes 0 Mfg. Des. Drill CHE45
Core Recovered 0 Ft. - Diam. - In. Inspected By Beddoo + Fisher
Soil Samples 1 3/8 In. Diam. 9 No. Classification By Beddoo
Soil Samples 2 In. Diam. 1 No. Classification By Fisher

DEPTH		CORE/SAMPLE		BLOWS PER FOOT CORE RECOVERED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1.0'	NO.	SIZE			
0.0'	1.0'			REC	Sample using 1 3/8" ID by 2' long split spoon sampler. First attempt drove a cobble from the surface in front of spoon. Remove large cobble and boulders from 0.0-1.5 manually. Second attempt yielded sample. Spin 4" casing to 5' clean out using 3 7/8" OD roller bit. Note penetration easy through out boring. Sample as above	Med. brown cml SAND and cf GRAVEL, trace SILT (wet, nonplastic) medium dense SW note petroleum odor. (offsite contaminant).
		S-1	1 3/8"	20%		
				8		
				11		
5.0'				9	Spin casing to 10.0' clean out using roller bit.	Med. grey CLAY and SILT, little ORGANICS (grass, wood chips) (saturated, plastic) soft CL Note odor of petroleum (offsite contaminant) and sulphur (natural).
		S-2	1 3/8"	65%		
				3		
				1		
7.0'				2		
				2		
10.0'						

GENERAL REMARKS:

Elevations as surveyed in the field by
ATL using benchmark near FD-5

All soil sampling performed in accordance with ASTM D1586 except as noted. (US-1 and US-2: ASTM D1587)

DEPTH		CORE/SAMPLE		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS
10'	2'	NO	SIZE	REMARKS		
12.0'	5-3	1 3/8"	100%	DEC 2 3 3 3	Sample using 1 3/8" ID by 2' long split spoon Sampler. Explorations end 2/11/87	Med. grey-brown SILT, little ORGANICS (grass, wood chips), trace CLAY,
15.0'					Explorations begin 2/12/87 Spin 4" casing to 15'; noting slower penetration indicating sand/gravel layers. Clean out with 3 7/8" OD roller bit	trace F. SAND. (wet, very slightly plastic) medium stiff <u>ML</u> Note odors of petroleum (offsite contaminant) and sulphur (natural).
17.0'	5-4	1 3/8"	40%	3 3 3 4	Sample as above.	Med. grey SILT, little med SAND, trace CLAY (sandy, very slightly plastic)
20.0'					Spin casing to 20' noting continued slow penetration. Clean out with roller bit.	Medium stiff <u>ML</u>
21.9'	5-5A	1 3/8"	100%	2 1 2 2	Sample as above	Med. grey CLAY, some SILT, little SHELL FRAGMENTS,
22.0'	5-5B				Explorations end 2/12/87 Explorations begin 2/17/87 Note inspector change to DM Fisher. ROLLER BIT IN OPEN HOLE	(wet, plastic) soft <u>SL</u> Dark brown ORGANICS (wood chips) and SILT, trace CLAY (wet, very slightly plastic) soft <u>OL</u>
25.0'						
27.0'	5-6	1 3/8"	90%	9 7 8 7		GREY, CLAY, SOME SILT, LITTLE SHELL FRAGMENTS (WET, PLASTIC) STIFF, <u>CL</u>

DEPTH	CORE/SAMPLE		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS
	NO.	SIZE	REMARKS	REMARKS	
27.0					
28.0					
30.0					
32.0	S-7	1 3/8"	55%	11 11 13 13 Sample using Split Spoon. Undisturbed sample not taken as drilling consistency and blow counts indicated attempt would be unsuccessful. END 2/17/87, START 2/18/87	GREY, CLAY, SOME SILT, LITTLE SHELLS, FRAGMENTS (WET, PLASTIC) STIFF, CL
35.3					
36.9	UD-1	3"	100%	—	
40.0					
42.0	S-8	1 3/8"	100%	8 7 7 7	GREY SILTY CLAY (WET, PLASTIC) STIFF CL-ML

DEPTH	CORE/SAMPLE			BLOW PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	N. Z	NO.	SIZE			
45.0				REC		
47.0		UD-2	3"	100%	3" OD PUSHED TUBE SAMPLER	GREY SILTY CLAY (WET, PLASTIC) STIFF <u>CL-ML</u>
48.0						
50.0		S-9	1 3/8"	100%	2" OD DRIVEN SPLIT SPOON END 2/18/87, START 2/19/87	As ABOVE
54.3					2" ID core barrel. Note: Drill rig had only 50 ft of steel available. Core barrel was used in an attempt to advance the boring without losing significant amounts of time.	STIFFER MATERIAL @ 52' (noted change in drilling consistency - no sample retained.)
56.5		S-10	2"	100%	2" ID core barrel Note: Material felt to be DENSE based on consistency while advancing the core barrel. BORING TERMINATED @ 56.5	BROWN-GREY F. SANDY SILT, TRACE CLAY (DRY-MOIST, Non PLASTIC) <u>ML-SM</u>

FIELD LOG OF UNDISTURBED SAMPLING IN DRILL HOLES

SITE ROUGHANS POINT HOLE NO. FD-87-21 DATE 2-18-87SAMPLE NO. UD-1 (35.3) INSPECTOR FISHER DRILLER CAMARIDGE Y BURNHAM

A	Total Length of Casing	20.4'	
B	Casing Length above Ground	0.4'	
C	Depth of Bottom of Casing (Below Ground) (A-B)	20.0'	
D	Length of Sampler and Drill Rods	38.0'	
E	Drill Rods Length above Ground	2.7'	
F	Depth of Bottom of Clean-Out Auger (below ground) (D-F)	35.3'	
G	Distance of Bottom of Auger above or below Casing (F-C)	15.5'	
		Drill Rods, (1)	Piston Rods, (2)
H	Total Length, Sampler and Rods	38.0'	N/A
I	Length of Rods above Ground	2.7'	N/A
J	Depth of Bottom of Sampler (below ground) (H-I) (1) & (2), (Depth of Top of Sample)	35.3'	N/A
K	Penetration of Sampler, (K-F) (1)	1.6'	N/A
L	Penetration or Swell of Piston (K-F) (2)	N/A	N/A
Data after Jacking			
M	Length of Sampler and Piston Rods above Ground	1.1'	N/A
N	Length of Drive (I-M) (1)	1.6'	
O	Piston Displacement (I-M) (2)	N/A	
P	Length of Sample Recovered	2.1'	
Q	Length of Sample Lost	GAIN 0.5' (CAVE IN)	
R	Amount of Sample Recovered, $\%, \frac{P}{N} \times 100$	100%	
S	Type and Size of Sampler	3" OD X 2.9' SOLID TUBE SAMPLER	
T	Method and Time of Penetration	HYD. DOWN PRESSURE (SEE NOTE*)	
U	Type of Materials Sampled	ML	
Other Notes and Remarks: * 450 PSI @ 22.43" PUSH, NOTED HARD PUSH THE FIRST 1.0' (500 PSI) WAITED 10 MIN, TURNED ROD & PULLED			

FIELD LOG OF UNDISTURBED SAMPLING IN DRILL HOLES

SITE ROUGHAN'S POINT HOLE NO. FD-87-21 DATE 2-18-87SAMPLE NO. UD-2 (45.0') INSPECTOR FISHER DRILLER CAMALOGUE
BURNHAM

A	Total Length of Casing	20.4'	
B	Casing Length above Ground	0.4'	
C	Depth of Bottom of Casing (Below Ground) (A-B)	20.0'	
D	Length of Sampler and Drill Rods	48.0'	
E	Drill Rods Length above Ground	3.0'	
F	Depth of Bottom of Clean-Out Auger (below ground) (D-F)	45.0'	
G	Distance of Bottom of Auger above or below Casing (F-C)	25.0'	
		Drill Rods, (1)	Piston Rods, (2)
H	Total Length, Sampler and Rods	48.0'	N/A
I	Length of Rods above Ground	3.0'	N/A
J	Depth of Bottom of Sampler (below ground) (H-I) (1) & (2), (Depth of Top of Sample)	45.0'	N/A
K	Penetration of Sampler, (K-F) (1)	2.0'	N/A
L	Penetration or Swell of Piston (K-F) (2)	N/A	N/A
Data after Jacking			
M	Length of Sampler and Piston Rods above Ground	1.0'	N/A
N	Length of Drive (I-M) (1)	2.0'	
O	Piston Displacement (I-M) (2)		N/A
P	Length of Sample Recovered	2.7	
Q	Length of Sample Lost	GAIN 0.7 (CAVE IN.)	
R	Amount of Sample Recovered, $\%, \frac{P}{N} \times 100$	100%	
S	Type and Size of Sampler	3" OD x 2.9' SOLID TUBE SAMPLER	
T	Method and Time of Penetration	HYD DOWN PRESSURE (SEE NOTE)	
U	Type of Materials Sampled	Grey Silty Clay CL-ML	
Other Notes and Remarks: * PUSH PRESSURE 450ps. @ 2110 HRS, WAITED 10 MIN, TURNED ROD + PULLED			

Site: Roughan's Point

Boring No: E 087-21


SUBSURFACE WATER OBSERVATIONS


[illegible]

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH

Atlantic Ocean \approx 



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Roughan's Point, Revere MA PROJECT NO. D.O. #0018
 Hole No. FD87-22 Dim. (Casing) 3 1/4" ID ^{Hollow Stem} Auger Page 1 of 4 Pages
 Co-ordinates: X see sketch Boring Started 2/6/87
 Drilled by Cambridge & Burdham Boring Completed 2/16/87
 Report Submitted _____

Purpose of Exploration determine foundation conditions for proposed
revetments, sluice gate and earth berms.

Elevation Top of Hole 5.80 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 22.5 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole -16.7 M.S.L.
 Total Rock Drilled 0 Feet
 Total Depth of Hole 22.5 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Diam. _____ In.
 Soil Samples 1 3/8 In. Diam. 4 No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth _____

Depth		Method of Drilling and Type of Bit Used
From	To	
0	6	RIP RAAS REMOVED BY BACKHOE
6	11	3 1/4" ID AUGER + ROLLER BIT*
11	22.5	OPEN HOLE, ROLLER BIT*
		*includes 1 3/8" split spoon sampling every 5'

INDEX

Ground Water _____ Back of Page _____
 Boring Location Sketch _____ Back of Page 4
 Overburden Record _____ Page 2-3
 Rock Drilling _____ Page _____
 _____ Page _____
 _____ Page _____

Prepared by P.M. Fisher Field Data _____ Lab. Data _____
 Submitted by Atlantic Testing Labs, Ltd.

Site Roughan's Point, Revere MA Page ² of 4 Pages
 Boring No. FD87-23 Desig. U Diam. (Casing) 3 1/4" ^{Hollow} stem
 Co-ordinates: X see sketch X ^{Auger}

Co-ordinates: ~~N~~ see sketch ~~E~~

DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
O.D. ¹	I ^a -2'	NO.	SIZE	DEPTH RANGE		
				DEC	Six feet of boulders removed by subcontracted track backhoe	Boulders (rip rap) 1-10 ft ³ in size; interstitial material air.
6.0'					Explorations end 2/10/87	
				11	START 2/10/87	GRET GRAVELLY
				13	1 3/8 x 2' SPLIT SPOON	cmf SAND, TRACE
		S-1	1 3/8	45%	9 3 1/4" ID Hollow Stem Auger	SILT (Moist, Non Plastic)
8.0				11	Augering difficult throughout boring.	MEDIUM DENSE, SW
9.0						

GENERAL REMARKS:
Elevations as determined in the field by ATC
using benchmark near FD-3 (FD87-20)
All soil sampling performed in accordance with ASTM
D1586 except as noted.


DEPTH	CORE/SAMPLE			BLOW PER FT	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO	SIZE	PERCENT			
11.0				REC		
	S-2	1 3/8	90%	26 42 80 74	1 3/8" X 2' SPLIT SPOON, OPEN HOLE USING 3" ROLLER BIT	BROWN + GREY SILTY F. SAND, SOME GRAVEL (MOIST, SLIGHTLY PLASTIC) DENSE, <u>SP-SM</u>
13.0						
14.5						
16						
	S-3	1 3/8	45%	27 35 38 80	As Above	GREY, CLAYEY SAND, LITTLE GRAVEL, LITTLE SILT (MOIST, PLASTIC) DENSE, <u>SC</u>
18						
21						
	S-4	1 3/8	15%	45 60 57	As Above	As Above
22.5						
					BORING TERMINATE @ 22.5	

Site: <u>Roughan's Point</u>		SUBSURFACE WATER OBSERVATIONS				
Boring No: <u>FD87-22</u>						
DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER	ELEVATION WATER	REMARKS
2/16/87	8:40P	—	22.5'	0.0'	5.80'	Note: Drilling method used water to advance the 3 7/8" OD roller bit. Water was consistently at the surface during drilling. Boring was advanced through dense, relatively impermeable material. Returning tide forced us offsite before we could measure any appreciable drop of the head in the boring.

Note: Depths are in feet below original ground

Not to Scale

BORING LOCATION SKETCH



Note: As-built boring location is the requested location.

SECTION 9

OTHER RECORDS TAKEN

a. Survey Notes

ROUGHAN'S POINT

CRAN 40

1987

JAN 6,

~~1986~~

M. MONTGOMERY

T. BEDDOE

①	BS	FS	Elev.
BMC HIGH			
Sy Top Wall	1.56	18.87	17.31
TTPT-1		11.34	7.53
BS TTPT-1	1.11	8.64	7.53
FD-R		6.62	2.02
FD-R T		12.40	-3.76
FD-R U		2.83	5.81
TTPT-2		5.96	2.68
TTPT-2	9.805	12.49	2.68
FD-XS		2.37	10.12
TTPT-3		8.52	3.97
TTPT-3	6.61	10.58	3.97
FD-P		12.74	-2.16
FD-Q		5.18	5.40
FD-O		2.85	7.73
TTPT-4	1.93	9.66	7.73
FD-N		12.97	-3.31
FD-M		8.68	8.98
TTPT-5		0.80	8.86
	21.015		

②	BS	FS	Elev.
TTPT-5	7.04	15.90	8.86
TTPT-6		9.96	5.94
TTPT-6	0.695	6.64	5.94
FD-K		5.78	0.86
FD-L		2.69	3.95
FD-I		8.16	-1.52
FD-J		5.10	1.54
TTPT-7		4.32	2.32
TTPT-7	3.56	5.88	2.32
FD-G		7.47	-1.59
FD-H		5.07	0.81
FD-F		4.57	1.31
FD-E		5.90	-0.02
TTPT-8		0.90	4.98
TTPT-8	10.925	15.91	4.98
FD-C		8.18	7.73
FD-D		4.22	11.69
Temp BM Top Wall		0.76	15.15
T.BM	3.30	18.45	15.15
FD-B		6.50	11.95
FD-A		8.57	9.88

③	T. B. M	TO	BEG. BM	
	BS		FS	ELEV
T. B. M.	0.26	15.41		15.15
TTPT 9			6.635	8.78
TTPT-9	6.53	15.31		8.78
TTPT-10			5.20	10.11
TTPT-10	4.385	14.50		10.11
TTPT-11			5.02	9.48
TTPT-11	8.34	17.82		9.48
BM on wall checked by			0.55	17.27
	66.050		62.815	
	- 3.300		62.200	
	<u>62.750</u>		<u>.005</u>	

17.31
17.27
104'

	BS	FS	ELEV
TEMP			
R. Mon wall	3.30	18.45	15.15
TTPT-1		7.555	10.90
TTPT-1	7.235	18.13	10.80
FD-V		8.36	9.77
TTPT-1	8.12	19.02 17.87	10.90 18.87
TTPT-2		0.945	18.87 18.87
TTPT-2	9.68	27.75 26.62	18.07 16.94
TTPT-3		0.36	27.39 27.26
TTPT-3	3.325	30.72 29.57	27.39 26.26
TTPT-4		10.53	20.19 19.06
TTPT-4	2.60	22.79 21.66	20.19 19.06
TTPT-5 END GRAD TAIL		9.82	12.97 11.84
TTPT-5	0.53	13.50 12.32	12.97 11.84
FD-W		8.12	5.38 4.25

BOLING ELEVATIONS ROUGHAN'S POINT

CK CD 020

ELEV. by M. MONTGOMERY + T. BEDDOE JAN 6, 1987

FD - A = 9.90

B = 12.00

C = 7.70

D = 11.70

E = 0.00

F = 1.30

* G = -1.60

H = 0.80

* I = -1.50

J = 1.50

K = 0.90

L = 4.00

M = 1.00

* N = -3.30

O = 7.70

* P = -2.20

Q = 5.40

R = 2.00

S = 10.10

* T = -3.80

U = 5.80

V = 9.80

W = 5.40

CC, TRAPERS B.

PAT. S.

* - THESE ELEVATIONS ARE MINUS ELEVATIONS

MDM 1/8/87

b. Letter to Ms. Dorothy Scholwin

ATLANTIC TESTING LABORATORIES, LIMITED

Sustaining Member—N.Y.S. Society of Professional Engineers

at

January 9, 1987

Box 29
Canton, N.Y. 13617
(315) 386-4578

Box 356
Cicero, N.Y. 13030
(315) 699-5281

Mrs. Dorothy Scholwin
156 Broad Sound
Revere, MA 02151

Re: Roughans Point Coastal Flood Protection Study

Dear Mrs. Scholwin:

Atlantic Testing Laboratories is under contract with the New England Division of the Army Corps of Engineers, Waltham, MA, to provide geotechnical exploratory work and related services for various projects in the New England and New York areas.

We are currently involved with a project in your area to determine foundation conditions for proposed revetments, sluice gates and earth berm for the Roughans Point Coastal Flood Protection Study.

Our firm's task regarding this project involves retrieving soil samples and evaluating bearing capacity of the underlying soils to insure the structural integrity of the proposed revetments.


Soil samples are taken at predetermined locations (see attached location drawing) to give an overall view of the subsurface conditions along the revetments.

Six of these sampling points require that we cross your beach property to reach these sampling points. None of the sampling points are on your property.

We respectfully request that you allow our sampling crews to cross your beach property. We will notify you each time we cross your property. Our crews would cross at low tide and stay well out on the beach area. Please be assured we will not cause any damage to your property.

Thank you for your consideration in this matter.

Respectfully submitted,


Spencer F. Thew, P.E./L.S.
President